

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		0004 L1C 90% FED 10% STATE	0011 L1C 90% FED 10% STATE	0040 L1C 90% FED 10% STATE	0021 L1C 90% FED 10% STATE
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	21	21			
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	10	10			
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	49	49			
84200804	REMOVAL OF POLE FOUNDATION	EACH	35	35			
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1			
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1			
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1	1			
86300300	CONTROLLER CABINET TYPE III	EACH	1			1	
86300305	CONTROLLER CABINET TYPE III, SPECIAL	EACH	1	1			
* 87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	3818	3818			
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 IC	FOOT	8550	8550			
87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	7	7			
87800215	CONCRETE FOUNDATION, TYPE D	EACH	1			1	
88600100	DETECTOR LOOP, TYPE I	FOOT	727			727	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1			
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	10	10			
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	11732	11732			
* K1005421	SEEDING (SPECIAL)	ACRE	7.25	7.25			
* X0323014	ELECTRIC CABLE IN CONDUIT, CONOGA-30003	FOOT	1300			1300	
* X0323015	PIEZO ELECTRIC AXLE SENSOR, CLASS II	FOOT	66			66	
X0323150	JUNCTION BOX, ALUMINUM, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	4	4			
* X0325073	MODIFY EXISTING CONTROLLER CABINET TYPE B	EACH	1	1			
* X0325076	WIDE AREA NETWORK	L SUM	1	1			
* X0325077	FIBER OPTIC UTILITY MARKER	EACH	29	29			
X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	270.9	270.9			
X0325482	REMOVE EXISTING ITS EQUIPMENT	EACH	1	1			
X0325483	SFP-GE-L SFP MODULE	EACH	1	1			
X0325484	SFP-GE-Z SFP MODULE	EACH	2	2			
* X0325487	WIRED COMMUNICATION DATA CONVERTOR	EACH	1	1			
X0326091	LIGHT POLE, STEEL 50 FT. WITH CAMERA LOWERING SYSTEM	EACH	2	2			
X0326092	RELOCATE CLOSED CIRCUIT TELEVISION SURVEILLANCE CAMERA SYSTEM	EACH	2	2			

\* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -		270	60-1B-1	MADISON	712	13			
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 76A91				
	PLOT DATE = #DATE#	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							