

SEEDING SCHEDULE										
LOCATION	SEEDING, CLASS 2A	SEEDING, CLASS 3A	SEEDING, SPECIAL	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING (2 APPLICATIONS)	STONE RIPRAP, CLASS A3
STATION	ACRE	ACRE	ACRE	POUND	POUND	POUND	ACRE	SQ YD	POUND	SQ YD
STAGE 1										
EX 270 STA 150+00 TO PR 270 STA 1177+02 - RT		1.80		162	162	162	3.6	8690	359	
PR WATERWORKS RD STA 1410+00 TO 1412+83 - LT	0.02			2	2	2	0.06		4	
PR WATERWORKS RD STA 1410+00 TO 1445+00 - RT	2.38			214	214	214	7.14		476	
PR WATERWORKS RD STA 1412+95 TO 1415+62 - LT		0.20		18	18	18	0.4	944	39	
PR WATERWORKS RD STA 1415+62 TO 1422+13 - LT	0.33			30	30	30	0.99		66	
PR WATERWORKS RD STA 1422+04 TO 1445+00 - LT	1.18			106	106	106	3.54		236	
LEVEE AREA										
TOP OF LEVEE			1.05	95	95	95	3.15		210	2713
CHOUTEAU PLACE RD AREA	0.25		0.54	71	71	71	1.57	3875	158	
SOUTH OF LEVEE AREA			1.43	129	129	129	3.64	3161	286	
WEST OF LEVEE RD AREA			0.41	37	37	37	1.23		82	
SOUTH ACCESS RD AREA			1.19	107	107	107	2.95	2986	238	
STAGE 2										
RAMP P4 - STA 11228+86 TO 11233+94 - LT	0.79			71	71	71	2.37		158	
STAGE 3										
PR 270 - STA 1158+00 TO 1192+93 - LT		6.70		603	603	603	13.4	32430	1340	
PR 270 - STA 1192+43 TO 1192+80 - LT/RT	0.07			6	6	6	0.21		14	
PR RAMP P1 - STA 21181+45 TO RAMP P1 STA 21194+48 - RT		0.99		89	89	89	2.0	4806	199	
RAMP P4 - STA 11229+00 TO END OF RAMP P4 - RT	2.37			213	213	213	7.11		474	
STAGE 4										
PR 270 - STA 1158+00 TO 1178+13 - MEDIAN	0.64			58	58	58	1.92		128	
STAGE 5										
EX 270 STA 150+02 TO PR 270 STA 1192+73 - RT		8.95		805	805	805	17.9	43306	1790	
PR 270 - STA 1168+00 TO 1191+85 - RT	6.54			589	589	589	19.62		1308	
PR 270 STA 1210+00 TO RAMP P4 STA 11229+00 - RT	5.05			455	455	455	15.15		1010	
RAMP P1 - STA 21156+73 TO 21181+45 - RT	7.01			631	631	631	21.03		1402	
RAMP P1 - STA 21164+24 TO 21188+04 - LT	3.34			301	301	301	10.02		668	
TOP OF LEVEE										
CHOUTEAU PLACE RD AREA			1.05	95	95	95	3.15	492	210	
SOUTH OF LEVEE AREA			0.10	9	9	9	0.20	3161	20	
STAGE 6										
PR 270 - STA 1221+48 TO 1231+32 - RT	0.64			58	58	58	1.92		128	
STAGE 7										
PR 270 - 1224+24 TO 1231+57 - MEDIAN	0.12			11	11	11	0.36		24	
SUBTOTAL										
	30.73	18.63	7.20	5091	5091	5091	147.45	103851	11312	2713
10% INCREASE										
								10395		
TOTAL										
	30.7	18.6	7.2	5091	5091	5091	147.5	114236	11312	2713

TEMPORARY DITCH CHECKS SCHEDULE		
STATION	OFFSET	TEMPORARY DITCH CHECKS
		FOOT
STAGE 1		
WATERWORKS RD		
1441+38	24.0' RT	16.6
CHOUTEAU PLACE RD		
177+68	14.5' RT	14.6
177+86	15.3' RT	14.6
178+04	16.8' RT	14.6
178+21	18.9' RT	20.6
178+39	21.1' RT	26.6
STAGE 2		
1170+63	130.4' LT	20.1
1173+26	134.1' LT	19.6
1175+89	139.9' LT	19.6
1176+20	142.0' LT	18.7
1179+20	141.9' LT	28.6
1183+92	155.1' LT	39.4
1186+80	197.9' LT	39.4
1187+20	204.9' LT	44.5
1162+24	1.5' RT	20.5
1165+58	0.8' RT	20.5
1168+91	1.4' RT	20.5
1174+19	1.0' RT	20.5
STAGE 5		
1218+69	49.1' LT	24.4
1219+04	50.0' LT	24.4
1219+39	54.5' LT	24.4
1219+73	55.5' LT	24.4
1220+08	57.9' LT	22.5
1220+42	62.2' LT	22.5
1220+77	64.9' LT	22.5
1221+12	67.8' LT	22.5
1221+46	70.1' LT	22.5
1221+81	72.9' LT	22.5
1222+19	74.6' LT	20.5
1222+61	78.1' LT	20.5
1223+04	80.0' LT	20.5
1223+46	84.3' LT	20.5
1223+88	88.7' LT	20.5
1224+66	96.9' LT	18.6
1225+58	110.0' LT	20.5
1226+50	124.0' LT	20.5
1227+61	135.2' LT	20.5
1228+48	151.9' LT	20.5
1229+48	179.6' LT	20.5
STAGE 6		
1227+29	101.3' RT	20.5
1227+53	107.1' RT	20.5
1227+77	113.3' RT	20.5
1228+01	119.9' RT	20.5
1228+17	124.7' RT	20.5
1228+34	130.0' RT	20.5
1228+50	135.4' RT	20.5
1228+66	140.7' RT	20.5
1228+83	147.0' RT	20.5
TOTAL		
		1060

INLET AND PIPE PROTECTION SCHEDULE		
STATION	OFFSET	INLET AND PIPE PROTECTION
		EACH
STAGE 1		
EX I-270		
150+00	LT	1
PR I-270		
1155+25	RT	1
1155+78	1' LT	1
1156+30	RT	1
1179+08	78' RT	1
WATERWORKS ROAD		
1414+43	35' LT	1
1418+71	21' RT	1
1425+68	32' LT	1
1430+07	33' RT	1
LEVEE ROAD		
342+29	138' RT	1
CHOUTEAU PLACE RD		
177+18	54' LT	1
STAGE 2		
PR I-270		
1159+99	2' RT	1
1170+01	23' RT	1
1172+53	34' RT	1
1178+20	4' LT	1
1178+20	4' RT	1
1180+00	4' LT	1
1180+00	4' RT	1
1182+00	4' LT	1
1182+00	4' RT	1
1184+00	4' LT	1
1184+00	4' RT	1
1186+00	4' LT	1
1186+00	4' RT	1
1188+00	4' LT	1
1188+00	4' RT	1
1190+00	4' LT	1
1190+00	4' RT	1
1214+00	4' LT	1
1214+00	4' RT	1
1216+00	4' LT	1
1216+00	4' RT	1
1218+00	4' LT	1
1218+00	4' RT	1
RAMP P1		
21191+50	6' RT	1
21189+00	6' RT	1
21188+95	2' RT	1
21186+50	6' RT	1
21185+45	2' RT	1
21184+00	34' RT	1
21184+00	6' RT	1
21183+95	2' RT	1
21181+00	2' RT	1
21169+06	43' RT	1
21168+71	21' RT	1
21168+95	119' LT	1
RAMP P4		
11232+00	47' LT	1
11232+92	120' RT	1
STAGE 3		
PR I-270		
1220+00	4' RT	1
1220+00	3' LT	1
STAGE 4		
PR I-270		
1160+00	LT	1
1170+00	RT	1
1222+00	5' RT	1
1222+00	3' LT	1
1226+29	2' RT	1
1230+93	1' RT	1
1231+75	10' LT	1
1231+71	10' RT	1
TOTAL		
		58

PERIMETER EROSION BARRIER SCHEDULE	
LOCATION	PERIMETER EROSION BARRIER
STATION	FOOT
STAGE 1	
EX 270 STA 149+99 TO PR 270 STA 1177+02 - RT	2676
PR 270 - STA 1164+82 TO 1170+79 - RT	580
PR 270 - STA 1215+50 TO 1221+37 - LT	934
PR 270 - STA 1215+86 TO 1221+01 - LT	531
PR 270 - STA 1190+70 TO 1192+80 - RT/LT	622
PR RAMP P4 STA 11233+30 TO EX RAMP P4 STA 17+93 - RT	314
PR WATERWORKS RD - STA 1400+00 TO 1441+99 - RT	200
PR WATERWORKS RD - STA 1410+00 TO 1412+79 - LT	287
PR WATERWORKS RD - STA 1413+05 TO 1417+21 - LT	420
PR WATERWORKS RD - STA 1413+05 TO 1423+62 - LT	911
PR WATERWORKS RD - STA 1422+28 TO 1445+10 - LT	2531
PR WATERWORKS RD - STA 1442+83 TO 1445+10 - RT	219
WEST OF LEVEE RD AREA	1766
NORTH OF N. ACCESS RD AREA	814
SOUTH OF LEVEE AREA	1037
SOUTH ACCESS RD AREA	647
STAGE 2	
PR 270 - STA 1158+00 TO 1168+49 - LT	1066
PR 270 - STA 1211+63 TO 1221+02 - RT/LT	1108
PR RAMP P1 - STA 21180+86 TO 21184+23 - RT	344
PR RAMP P4 - STA 11225+50 TO 11234+08 - RT	834
STAGE 3	
PR RAMP P4 STA 11218+72 TO EX IL RTE 3 STA 1373+33 - LT	2003
STAGE 4	
EX 270 STA 150+02 TO PR 270 STA 1191+01 - RT	4085
PR 270 STA 1164+96 TO PR 270 STA 1169+04 - RT	397
STAGE 5	
EX RAMP P1 STA 22+60 TO EX IL RTE 3 STA 1341+46 - RT	2411
PR 270 - STA 1209+96 TO 1218+72 - RT	854
TOTAL	
	27589

FILE NAME = DB76991-Sht-Eros-schedule.dgn
VOLKERT

USER NAME = untitled
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 3/15/2011

DESIGNED - MPW
 DRAWN - CJS
 CHECKED - PMK
 DATE - 3/18/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

EROSION CONTROL SCHEDULE

SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. NA TO STA. NA

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-1B-1	MADISON	712	211
			CONTRACT NO. 76A91	
ILLINOIS FED. AID PROJECT				