FINAL SURVEY	NOTE BOOK	NO.
SURVEYED		BY
PLOTTED		DATE
TEMPLATE		
AREAS		
AREAS CHECKED		

ORIGINAL SURVEY	NOTE BOOK	NO.
SURVEYED		BY
PLOTTED		DATE
TEMPLATE		
AREAS		
AREAS CHECKED		

180+81.00

EX. EASEMENT

419.19 — 419.37 — 2.0% — 5.0% — 4:1

CUT =12.56
TOPSOIL EXC =0.85
FILL =0.00

180+50.00

419.34 — 419.52 — 2.0% — 5.0% — 4:1

CUT =12.99
TOPSOIL EXC =0.91
FILL =0.00

180+00.00

419.90 — 420.08 — 2.0% — 5.0% — 4:1

CUT =17.02
TOPSOIL EXC =0.31
FILL =0.00

179+50.00

421.14 — 421.32 — 2.0% — 5.0% — 4:1

CUT =13.65
TOPSOIL EXC =1.17
FILL =0.00

179+00.00

SEE I-270 XSECTIONS FOR MSE WALL HEIGHT AND FINAL GRADING

423.08 — 423.24 — 2.0% — 4.6% — 1.8% — 4:1 — 4:1 — 420.11

CUT =27.48
TOPSOIL EXC =20.03
FILL =7.62

178+50.00

SEE I-270 XSECTIONS FOR MSE WALL HEIGHT AND FINAL GRADING

425.69 — 425.86 — 2.0% — 4.7% — 1.9% — 4:1 — 4:1 — 428.86

CUT =0.25
TOPSOIL EXC =14.33
FILL =77.73

425 420 415 410 0 10 20 30 40 50 60 70 80 90

FILE NAME =	USER NAME = malopez	DESIGNED SJM	REVISED -
0876D91-sht-xs-chouteau.dgn		DRAWN BAH	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = 3/17/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
CHOUTEAU PLACE ROAD

SCALE: | SHEET NO. OF SHEETS | 178+50.00 | 180+81.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-1B-1	MADISON	712	631
		CONTRACT NO. 76A91		
	ILLINOIS FED. AID PROJECT			