

# SUMMARY OF QUANTITIES

STP (L24E)  
80% FED.  
20% STATE

HSIP (LS3E)  
90% FED.  
10% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED. 20% STATE MONROE	0005 80% FED. 20% STATE RANDOLPH	0021 90% FED. 10% STATE MONROE	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 MONROE	0005 RANDOLPH	0021 MONROE
X4420670	CLASS B PATCHES, TYPE I, 9 INCH (SPECIAL)	SQ YD	60		60		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5	
X4420672	CLASS B PATCHES, TYPE II, 9 INCH (SPECIAL)	SQ YD	107		107		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5	
X4420674	CLASS B PATCHES, TYPE III, 9 INCH (SPECIAL)	SQ YD	19		19		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5	
21400100	GRADING AND SHAPING DITCHES	FOOT	2957	2957			70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.5	0.5	
28000305	TEMPORARY DITCH CHECKS	FOOT	120	120			70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27.5	24.45	3.09		70300100	SHORT TERM PAVEMENT MARKING	FOOT	9187	8179	1008	
40600300	AGGREGATE (PRIME COAT)	TON	131	116.5	14.5		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	103583	92943.8	10639.2	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3683	3269.3	413.7		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1021	909	112	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1070	1057	13		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	91862	81222.8	10639.2	
40600990	TEMPORARY RAMP	SQ YD	290	272	18		* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	11722	11722		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7387	6555.43	831.57		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	424	377	47	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10			* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	66739	60684	6055		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	424	377	47	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	22810	19008	3802		X0325866	CENTER LINE - RUMBLE STRIP	FOOT	8290			8290
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	227	213.67	13.33		Z0010910	COLD MILLING (SPECIAL)	SQ YD	5427			5427
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	182	182			+ Z0076600	TRAINEES	HOUR	1,000	500	500	
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	203	171	32								
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	41		41								
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	81		81								
44201299	DOWEL BARS 1 1/2"	EACH	617		617								
44213100	PAVEMENT FABRIC	SQ YD	100		100								
44213200	SAW CUTS	FOOT	1488		1488								
44213204	TIE BARS 3/4"	EACH	25		25								
44213208	TIE BARS 1 1/4"	EACH	19		19								
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1177	1091	86								
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	5427			5427							
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2									
63200310	GUARDRAIL REMOVAL	FOOT	100	100									
64200105	SHOULDER RUMBLE STRIPS	FOOT	16281			16281							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	2								
67100100	MOBILIZATION	L SUM	1	0.5	0.5								
67201000	SEALING ABANDONED WATER WELLS	EACH	1	1									

\*SPECIALTY ITEM + 0042

FILE NAME *	USER NAME * #USER*	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 600	SECTION (S1.132/RS-4)	COUNTY *	TOTAL SHEETS 23	SHEET NO. 3
#FILE#		DRAWN - ---	REVISED - ---							
	PLOT SCALE = #SCALE*	CHECKED - ---	REVISED - ---							
	PLOT DATE = #DATE*	DATE - ---	REVISED - ---							
						SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		
										CONTRACT NO. 76B79

\* MONROE, RANDOLPH