℄ EX. MAIN ST.

CONSTRUCTION LIMITS

PROPOSED R.O.W.

CHAIN LINK FENCE, 6' - 1369'

℄ PROPOSED I-70

ROADWAY PAVING BY OTHERS

MATCH LINE STA. 176+00 SEE SHEET 41

GRADING LIMITS 54+00

176+96.45 119.26' RT

FURNISHING AND ERECTING DRAINAGE MARKERS

TWO ADDITIONAL FURNISHING AND ERECTING DRAINAGE MARKERS (NOT SHOWN) AT:
STA. 176+80.66 451.66' RT
STA. 177+10.34 447.32' RT

℄ PR. RAMP B

CHAIN LINK FENCE, 6' - 1,506'

CONSTRUCTION LIMITS

TEMPORARY FENCE, SEE REMOVAL PLANS FOR LOCATION. FENCE TO REMAIN IN PLACE AFTER CONSTRUCTION IS COMPLETE.

℄ IL RTE 3

STA. 93+00 SHEET NOT REQUIRED

MATCH LINE STA. 190+00 SEE SHEET 43

PC STA 183+32.89

PT STA 189+28.42

223.47'

36'

16'

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -
		DRAWN - JB	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT DATE = $DATE$	DATE - 02/04/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
I-70 CONNECTION

PROPOSED I-70
ROADWAY PLAN
STA. 176+00 TO STA. 190+00

SCALE: 1"=50' | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-1A	ST. CLAIR	190	42
		CONTRACT NO. 76C41		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\\DBCONN-PR-MOTIF1.DGN \\DBCONN-06-BORDER.DGN \\DBCONN-03-GEOMETRICS.DGN \\DBCONN-06-LEGEND.DGN \\DBCONN-06-MOTIF.DGN \\DBCONN-11-MOTIF1.DGN
2/04/2011 15:01:09 BDNOHLUD \\FS-08\41\VAULT\P-TRANS_07\22822\28968-201\CIVIL\CADD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 06\DBCONN-06-SHT-PLAN1-176802.DGN