UTILITY REMOVAL SCHEDULE

I-70 LOCATIONS							WATER MAINS						STORM SEWERS										UNKNOWN UTILITIES	GAS MAINS
ID SUFFIXES = SOURCE OF INFORMATION																								
A = SURVEY OR RECORD PLANS B = COMMERCIAL SEWER ATLAS C = PRIVATE SEWER ATLAS				DIAMETER - INCHES TOTALS - FEET			4" 1,038'	6" 6,610'	8" 6,197'	10" 7,001'	12" 1,209'	UNK. DIA.	6" 645'	8" 4,539'	10" 2,974'	12" 4,463'	15" 7,031'	16" 485'	18" 4,895'	24" 1,960'	36" 695'	UNK. DIA.	3,632'	869'
ID#	FROM STA.	OFFSET	LT/RT	TO STA	OFFSET																			
87C	189+20	18	LT	190+51	14	RT																172		
88C	190+22	262	RT	190+41	192	RT																72		
89C	190+55	262	RT	190+76	295	RT'																41		
90C	190+68	262	RT	190+72	240	RT																23		
91C	190+86	263	RT	190+90	239	RT																24		
92C	191+02	263	RT	191+09	221	RT																43		
93C	191+21	263	RT	191+43	297	RT																41		
94C	190+05	13	RT	190+19	54	RT																46		
95C	190+20	170	LT	190+19	15	RT																184		
96C	190+26	152	LT	190+23	84	RT																248		
97C	190+51	47	LT	190+50	45	RT																92		
98C	190+39	53	LT	190+64	53	LT																30		
99C	190+39	27	LT	190+63	27	LT																30		
100C	190+38	5	LT	190+63	5	LT																30		
101C	190+37	28	RT	190+64	28	RT																30		
102C	190+37	52	RT	190+63	52	RT																30		
103C	190+51	123	LT	192+57	154	RT																		458
104C	191+53	235	LT	191+73	149	RT																409		
105C	191+52	149	LT	191+89	144	LT																38		
106C	190+48	83	RT	190+59	122	RT																41		
SUB TOTALS (KNOWN DIA.)							593	4,329	4,273	4,507	781		248	1,762	593	893	1,278	88	1,324	968	695		3,632	869
REMOVAL OF UNKNOWN UTILITIES							445	265	224	290	50		47	330	283	425	684	47	425	118	0			
ASSUMED % BREAKOUT FROM WATER MAIN, STORM & SANITARY SEWERS (UNKNOWN DIAMETER)							0%	32%	27%	35%	6%	100%	2%	14%	12%	18%	29%	2%	18%	5%	0%	100%		
SUB TOTALS							0	2,015	1,700	2,204	378	6,298	350	2,447	2,097	3,146	5,069	350	3,146	874	0	17,478		
									SUM =	6,298'						SUM =	17,478'							

UNKNOWN DIA. REMOVALS DISTRIBUTED INTO ASSUMED SIZES (SEE NOTE 1)

(SEE NOTE 1)

REMOVAL OF UNKNOWN UTILITY

PAID FOR AS	LENGTH (FT)
WATER MAIN REMOVAL	
4"	445
6"	265
8"	224
10"	290
12"	50
SUBTOTAL	1,274
STORM SEWER REMOVAL	
6"	47
8"	330
10"	283
12"	425
15"	684
16"	47
18"	425
24"	118
36"	0
SUBTOTAL	2,358
FINAL TOTAL	3,632

NOTES:
1. SEE SPECIAL PROVISION FOR "GUIDELINES FOR UNDERGROUND UTILITY REMOVALS" FOR GUIDE TO REMOVALS OF UTILITIES WITH "UNKNOWN DIAMETER" OR FOR "UNKNOWN UTILITIES".