


- NOTES:**
1. SEE DRAWING ME-01 FOR ELECTRICAL SYMBOLS AND ABBREVIATIONS.
 2. THE EXISTING ROADWAY LIGHTING SYSTEM SHALL REMAIN IN OPERATION UNTIL THE PROPOSED ROADWAY LIGHTING SYSTEM HAS BEEN INSTALLED, ENERGIZED, TESTED AND ACCEPTED BY THE ENGINEER, UNLESS NOTED OTHERWISE.
 3. COORDINATE ALL WORK WITH IDOT CONTRACT NOS. 76C49, 76C50, 76C51, 76C52, 76C53, 76C55, 76C75, AND 76C76.
 4. REMOVE THE EXISTING CONDUITS AND JUNCTION BOXES ATTACHED TO STRUCTURE MADE OBSOLETE BY THE REMOVAL OF THE EXISTING HIGH MAST TOWERS ALL THE WAY BACK TO EXISTING IDOT LIGHTING CONTROLLER 2S. THE CONDUIT REMOVAL SHALL BE PAID FOR UNDER THE "REMOVE EXISTING CONDUIT ATTACHED TO STRUCTURE" PAY ITEM.
 5. DISCONNECT THE EXISTING SIGN LIGHTING ELECTRICAL FEED AND REMOVE CABLES BACK TO THE NEAREST SPLICE POINT. SIGN LUMINAIRES AND DISCONNECT SWITCH TO REMAIN FOR RECONNECTION TO THE PROPOSED LIGHTING CIRCUIT SHOWN ON RL-02.
 6. THE EXISTING IDOT LIGHTING TO REMAIN SOUTH OF ST. CLAIR IS FED FROM EXISTING IDOT LIGHTING CONTROLLER 2S. THIS LIGHTING MUST REMAIN IN SERVICE WITHOUT INTERRUPTION FOR THE DURATION OF THE CONTRACT.



FILE NAME =	USER NAME = jentzt	DESIGNED - WDS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LIGHTING PLANS EXISTING CONDITIONS AND DEMOLITION		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
\$FILE#	PLOT SCALE = 50,0001' / IN.	DRAWN - TL	REVISED -		SCALE: 1"=50'	SHEET NO. 1 OF 8 SHEETS	STA. 51+87.84 TO STA. 65+97.00	55/64	82-1L	ST. CLAIR	60	38
	PLOT DATE = 12/29/2010	CHECKED - JPC	REVISED -									
		DATE - JANUARY 4, 2011	REVISED -					FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 76C54	

EL-02