


- NOTES:**
- SEE DRAWING ME-01 FOR ELECTRICAL SYMBOLS AND ABBREVIATIONS.
 - SEE DRAWING ES-01 FOR HIGH MAST TOWER FOUNDATION SCHEDULE.
 - COORDINATE ALL WORK WITH IDOT CONTRACT NOS. 76C49, 76C50, 76C51, 76C52, 76C53, 76C55, 76C75, AND 76C76.
 - INSTALL PARALLEL CABLES IN A COMMON TRENCH.
 - JUNCTION BOX MOUNTED ON BRIDGE STRUCTURE FOR UNDERPASS LIGHTING POWER FEED SHALL BE INSTALLED AS SHOWN ON IDOT STANDARD LGT019. SEE DRAWING UL-01 FOR THE 9TH STREET UNDERPASS LIGHTING PLANS.
 - THE LOCATIONS OF THE PROPOSED CABLES, CONDUITS AND SLEEVES SHOWN ON THIS DRAWING ARE DIAGRAMMATIC ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE ALL WORK WITH OTHER CONCURRENT IDOT CONTRACTS SO THAT THE PROPOSED CABLES, CONDUITS AND SLEEVES SHOWN ON THIS DRAWING ARE INSTALLED IN A LOCATION THAT DOES NOT INTERFERE OR CONFLICT WITH EXISTING UTILITIES AND WORK DONE IN OTHER CONCURRENT IDOT CONTRACTS.
 - PVC CONDUIT SLEEVES SHALL BE INSTALLED AT ELEVATION 392.00 TO AVOID DAMAGE FROM FUTURE ROADWAY WORK IN CONTRACT NO. 76C52. ALL EXCAVATING, SHEETING, SHORING, MATERIALS AND LABOR NECESSARY FOR COMPLETE INSTALLATION OF THE PUSHED CONDUIT WILL NOT BE MEASURED FOR PAYMENT SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF THE "CONDUIT PUSHED, 4" DIA., PVC" PAY ITEM.
 - PVC CONDUIT SLEEVES SHALL BE INSTALLED AT ELEVATION 412.00 TO AVOID DAMAGE FROM FUTURE ROADWAY WORK IN CONTRACT NO. 76C51. ALL EXCAVATING, SHEETING, SHORING, MATERIALS AND LABOR NECESSARY FOR COMPLETE INSTALLATION OF THE PUSHED CONDUIT WILL NOT BE MEASURED FOR PAYMENT SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF THE "CONDUIT PUSHED, 4" DIA., PVC" PAY ITEM.
 - ROUTE THE PROPOSED LIGHTING CABLES IN TRENCH 50 FEET (MINIMUM) UP THE SLOPE AWAY FROM AND PERPENDICULAR TO THE I-64 ROADWAY AS SHOWN ON THE PLANS TO AVOID ANY CONFLICTS WITH THE FUTURE WORK IN CONTRACT NO. 76C52.
 - PROVIDE A SOLAR POWERED FLASHING BEACON ASSEMBLY FOR THE SIGN STRUCTURE AS SPECIFIED IN THE SPECIAL PROVISIONS AND AS DIRECTED BY THE ENGINEER. THE FLASHING BEACONS SHALL BE MOUNTED ON EACH SIDE OF THE SIGN PANEL AS SHOWN ON THE CONTRACT NO. 76C52 SIGNING PLANS. THE INSTALLATION OF THE FLASHING BEACON ASSEMBLY SHALL BE COORDINATED WITH THE NEW SIGN STRUCTURE AND PANEL WORK IN CONTRACT NO. 76C52.
 - PVC CONDUIT SLEEVE SHALL BE INSTALLED AT ELEVATION 397.00 TO AVOID DAMAGE FROM FUTURE ROADWAY WORK IN CONTRACT NO. 76C51. ALL EXCAVATING, SHEETING, SHORING, MATERIALS AND LABOR NECESSARY FOR COMPLETE INSTALLATION OF THE PUSHED CONDUIT WILL NOT BE MEASURED FOR PAYMENT SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF THE "CONDUIT PUSHED, 4" DIA., PVC" PAY ITEM.
 - PVC CONDUIT SLEEVE SHALL BE INSTALLED AT ELEVATION 398.00 TO AVOID DAMAGE FROM FUTURE ROADWAY WORK IN CONTRACT NO. 76C51. ALL EXCAVATING, SHEETING, SHORING, MATERIALS AND LABOR NECESSARY FOR COMPLETE INSTALLATION OF THE PUSHED CONDUIT WILL NOT BE MEASURED FOR PAYMENT SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF THE "CONDUIT PUSHED, 4" DIA., PVC" PAY ITEM.

MATCH LINE STA. 27+90.81
EB I-64 BASELINE
SEE DRAWING RL-03

MATCH LINE STA. 39+90.78
EB I-64 BASELINE
SEE DRAWING RL-05



FILE NAME = #FILE#	USER NAME = lantz	DESIGNED - WDS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LIGHTING PLANS PROPOSED WORK	F.A.I. RTE. 55/64	SECTION 82-1L	COUNTY ST. CLAIR	TOTAL SHEETS 60	SHEET NO. 49		
PLOT SCALE = 50.0001' / IN.		CHECKED - JPC	REVISED -			SCALE: 1"=50'	SHEET NO. 4 OF 8 SHEETS	STA. 27+90.81	TO STA. 39+90.78	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	
PLOT DATE = 12/29/2010		DATE - JANUARY 4, 2011	REVISED -			CONTRACT NO. 76C54						

RL-04