

# SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES |   |        | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE       |       |       | SUMMARY OF QUANTITIES |  |       | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE       |       |       |
|-----------------------|---|--------|------------------|------------------------------|-------|-------|-----------------------|--|-------|------------------|------------------------------|-------|-------|
| CODE NO               | ITEM  | UNIT   |                  | 0005<br>80%_EED<br>20%_STATE | ----- | ----- | CODE NO               | ITEM   | UNIT  |                  | 0005<br>80%_EED<br>20%_STATE | ----- | ----- |
| 20201200              | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL           | CU YD  | 1.8              | 1.8                          |       |       | 70100450              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201      | L SUM | 1                | 1                            |       |       |
| 40600200              | BITUMINOUS MATERIALS (PRIME COAT)                     | TON    | 13.2             | 13.2                         |       |       | 70100460              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306      | L SUM | 1                | 1                            |       |       |
| 40600300              | AGGREGATE (PRIME COAT)                                | TON    | 64               | 64                           |       |       | 70300100              | SHORT TERM PAVEMENT MARKING                          | FOOT  | 27684            | 27684                        |       |       |
| 40600895              | CONSTRUCTING TEST STRIP                               | EACH   | 1                | 1                            |       |       | 70300210              | TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS       | SO FT | 62.4             | 62.4                         |       |       |
| 40600985              | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD  | 3000             | 3000                         |       |       | 70300220              | TEMPORARY PAVEMENT MARKING - LINE 4"                 | FOOT  | 36021            | 36021                        |       |       |
| 40600990              | TEMPORARY RAMP  | SQ YD  | 150              | 150                          |       |       | 70300260              | TEMPORARY PAVEMENT MARKING - LINE 12"                | FOOT  | 351              | 351                          |       |       |
| 40603090              | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90           | TON    | 5329             | 5329                         |       |       | 70300280              | TEMPORARY PAVEMENT MARKING- LINE 24"                 | FOOT  | 46               | 46                           |       |       |
| 40603345              | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90          | TON    | 3553             | 3553                         |       |       | 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL                   | SO FT | 3076             | 3076                         |       |       |
| 40800020              | BITUMINOUS MATERIALS (PRIME COAT)                     | TON    | 1                | 1                            |       |       | *78000100             | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 62.4             | 62.4                         |       |       |
| 40800030              | AGGREGATE (PRIME COAT)                                | TON    | 3                | 3                            |       |       | *78000200             | THERMOPLASTIC PAVEMENT MARKING - LINE 4"             | FOOT  | 36021            | 36021                        |       |       |
| 40800050              | INCIDENTAL HOT-MIX ASPHALT SURFACING                  | TON    | 67               | 67                           |       |       | *78000600             | THERMOPLASTIC PAVEMENT MARKING - LINE 12"            | FOOT  | 351              | 351                          |       |       |
| 44004250              | PAVED SHOULDER REMOVAL                                | SQ YD  | 5.3              | 5.3                          |       |       | *78000650             | THERMOPLASTIC PAVEMENT MARKING - LINE 24"            | FOOT  | 46               | 46                           |       |       |
| 44201000              | CLASS B PATCHES, TYPE IV, 12 INCH                     | SQ YD  | 149              | 149                          |       |       | *78100100             | RAISED REFLECTIVE PAVEMENT MARKER                    | EACH  | 240              | 240                          |       |       |
| 44201294              | CLASS B PATCH - EXPANSION JOINT                       | FOOT   | 170              | 170                          |       |       | *78200410             | GUARDRAIL MARKERS, TYPE A                            | EACH  | 16               | 16                           |       |       |
| 44201296              | DEFORMED BARS - EXPANSION JOINT                       | EACH   | 110              | 110                          |       |       | *78201000             | TERMINAL MARKER - DIRECT APPLIED                     | EACH  | 4                | 4                            |       |       |
| 44201297              | DOWEL BARS 1"   | EACH   | 25               | 25                           |       |       | 78300200              | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL            | EACH  | 240              | 240                          |       |       |
| 44213200              | SAW CUTS  | FOOT   | 849              | 849                          |       |       | X4421021              | CLASS B PATCHES, TYPE IV, 12 INCH, SPECIAL           | SO YD | 138              | 138                          |       |       |
| 44213202              | TIE BARS 1"   | EACH   | 410              | 410                          |       |       | 20076600              | TRAINEES   | Hour  | 500              | 500                          |       |       |
| 44300200              | STRIP REFLECTIVE CRACK CONTROL TREATMENT              | FOOT   | 2100             | 2100                         |       |       |                       |  |       |                  |                              |       |       |
| 48102100              | AGGREGATE WEDGE SHOULDER, TYPE B                      | TON    | 353              | 353                          |       |       |                       |  |       |                  |                              |       |       |
| 48203100              | HOT-MIX ASPHALT SHOULDERS                             | TON    | 4708             | 4708                         |       |       |                       |  |       |                  |                              |       |       |
| 48300300              | PORTLAND CEMENT CONCRETE SHOULDERS 8"                 | SQ YD  | 5.3              | 5.3                          |       |       |                       |  |       |                  |                              |       |       |
| 50300225              | CONCRETE STRUCTURES                                   | CU YD  | 1.4              | 1.4                          |       |       |                       |  |       |                  |                              |       |       |
| 50800205              | REINFORCEMENT BARS, EPOXY COATED                      | POUND  | 291              | 291                          |       |       |                       |  |       |                  |                              |       |       |
| 60100080              | FRENCH DRAINS   | CU YD  | 1.8              | 1.8                          |       |       |                       |  |       |                  |                              |       |       |
| 60100085              | GEOTECHNICAL FABRIC FOR FRENCH DRAINS                 | SQ YD  | 5.3              | 5.3                          |       |       |                       |  |       |                  |                              |       |       |
| *63000001             | STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS     | FOOT   | 1104             | 1104                         |       |       |                       |  |       |                  |                              |       |       |
| *63100089             | TRAFFIC BARRIER TERMINAL, TYPE 6B                     | EACH   | 4                | 4                            |       |       |                       |  |       |                  |                              |       |       |
| *63100167             | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT    | EACH   | 4                | 4                            |       |       |                       |  |       |                  |                              |       |       |
| 63200310              | GUARDRAIL REMOVAL                                     | FOOT   | 1100             | 1100                         |       |       |                       |  |       |                  |                              |       |       |
| 64200105              | SHOULDER RUMBLE STRIPS                                | FOOT   | 25216            | 25216                        |       |       |                       |  |       |                  |                              |       |       |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A                       | CAL MO | 4                | 4                            |       |       |                       |  |       |                  |                              |       |       |
| 67100100              | MOBILIZATION  | L SUM  | 1                | 1                            |       |       |                       |  |       |                  |                              |       |       |

\*SPECIALTY ITEM ■ 0042

|             |                      |            |           |   |                              |   |                    |  |                 |             |
|-------------|----------------------|------------|-----------|---|------------------------------|---|--------------------|--|-----------------|-------------|
| FILE NAME = | USER NAME = #USER#   | DESIGNED - | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b> | F.A.P. RTE. 327   | SECTION 14, 15BS-1 | COUNTY CLINTON   | TOTAL SHEETS 21 | SHEET NO. 3 |
| #FILE#      | PLOT SCALE = #SCALE# | CHECKED -  | REVISED - |   |                              | SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____ |                    | FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT CONTRACT NO. 76E10 |                 |             |
|             | PLOT DATE = #DATE#   | DATE -     | REVISED - |   |                              |   |                    |  |                 |             |