

CLASS B PAVEMENT PATCHING SCHEDULE

LOCATION	LANE	LENGTH	WIDTH	AREA	TYPE II	TYPE III	SAWCUT	DOWELL BARS	PAVEMENT FABRIC
STATION	EB/WB	FEET	FEET	SQ. YDS.	SO. YDS.	SO. YDS.	FEET	EACH	SO. YDS.
(AREA 1)									
12+08	EB	6	12	8.0	8.0		36	20	
12+08	WB	6	12	8.0	8.0		36	20	
12+94	EB	6	12	8.0	8.0		36	20	
12+94	WB	6	12	8.0	8.0		36	20	
13+94	EB	6	12	8.0	8.0		36	20	
13+94	WB	6	12	8.0	8.0		36	20	
14+94	EB	6	12	8.0	8.0		36	20	
14+94	WB	6	12	8.0	8.0		36	20	
15+20	EB	6	12	8.0	8.0		36	20	
15+20	WB	6	12	8.0	8.0		36	20	
15+90	EB	6	12	8.0	8.0		36	20	
15+90	WB	6	12	8.0	8.0		36	20	
(AREA 2)									
27+36	EB	12	12	16.0		16.0	48	20	16.0
(AREA 3)									
41+29	EB	6	12	8.0	8.0		36	20	
41+29	EB	6	12	8.0	8.0		36	20	
41+29	WB	6	12	8.0	8.0		36	20	
41+29	WB	6	12	8.0	8.0		36	20	
41+84	EB	6	12	8.0	8.0		36	20	
41+84	EB	6	12	8.0	8.0		36	20	
41+84	EB	6	12	8.0	8.0		36	20	
41+84	WB	6	12	8.0	8.0		36	20	
41+84	WB	6	12	8.0	8.0		36	20	
42+35	EB	6	12	8.0	8.0		36	20	
42+35	EB	6	12	8.0	8.0		36	20	
42+35	EB	6	12	8.0	8.0		36	20	
42+85	EB	6	12	8.0	8.0		36	20	
42+85	EB	6	12	8.0	8.0		36	20	
43+36	EB	6	12	8.0	8.0		36	20	
43+36	EB	6	12	8.0	8.0		36	20	
43+86	EB	6	12	8.0	8.0		36	20	
43+86	EB	6	12	8.0	8.0		36	20	
43+86	WB	6	12	8.0	8.0		36	20	
44+37	EB	6	12	8.0	8.0		36	20	
44+37	EB	6	12	8.0	8.0		36	20	
44+37	WB	10	12	13.3	13.3		44	20	
44+37	WB	6	12	8.0	8.0		36	20	
44+78	EB	6	12	8.0	8.0		36	20	
44+78	EB	6	12	8.0	8.0		36	20	
44+78	WB	6	12	8.0	8.0		36	20	
44+78	WB	6	12	8.0	8.0		36	20	
SUB-TOTALS					317.3	16.0	1460.0	800.0	16.0
15% ANTICIPATED FAILURES						47.6	2.4	219	2.4
GRAND TOTALS					365	19	1679	920	19

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE. 9185	SECTION 10-1RS-1	COUNTY ST. CLAIR	TOTAL SHEETS 25	SHEET NO. 13
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---			SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. _____	ILLINOIS FED. AID PROJECT
PLOT DATE = #DATE#	DATE - _____	REVISED - ---								