

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE 0021				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONTROLLER*			
				2	3	4	5
66400305	CHAIN LINK FENCE, 6'	FOOT	37			37	
66407400	CHAIN LINK GATES, 6' X 8' DOUBLE	EACH	1			1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	1.25	.50	2.25	1
67100100	MOBILIZATION	L SUM	1	.25	.25	.25	.25
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	.44	.28		.28
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1				1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	.20	.40		.40
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1			1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	.50	.50		
80300100	LOCATING UNDERGROUND CABLE	FOOT	21410	5155		11320	4935
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1	
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	10			10	
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	370	95		70	205
81100582	CONDUIT ATTACHED TO STRUCTURE, 1 1/4" DIA., ALUMINUM	FOOT	895	755			140
81300310	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 8" X 6" X 4"	EACH	9	8			1
81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	1459	1294		20	145
81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	400	400			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	21410	5155		11320	4935
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	84	21	5	40	18
82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1			1	
83009100	LIGHT POLE, ALUMINUM, 45 FT. M.H., 4 FT. MAST ARM	EACH	6	3	2		1
83010300	LIGHT POLE, ALUMINUM, 50 FT. M.H., 8 FT. MAST ARM	EACH	78	18	3	40	17
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	546	126	21	280	119
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	78	18	3	40	17
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	84	21	5	40	18
84200804	REMOVAL OF POLE FOUNDATION	EACH	78	18	3	40	17
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1	
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1	

SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE 0021				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONTROLLER*			
				2	3	4	5
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1			1	
87300815	ELECTRIC CABLE IN TRENCH, SERVICE, NO. 6 3 C	FOOT	21410	5155		11320	4935
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1567	1352		70	145
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	45			45	
X7240311	RELOCATE EXISTING SIGN PANEL (SPECIAL)	EACH	15	4	3	6	2
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	.50	.50		
X0327260	BARBED WIRE FENCE, THREE STRAND	FOOT	45			45	
X8130125	REMOVE EXISTING JUNCTION BOX	EACH	9	8			1
X6010005	SHOULDER REMOVAL AND REPLACEMENT FOR ELECTRICAL WORK	FOOT	120			120	
X6640304	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	20				20