

# SUMMARY OF QUANTITIES

90% FEDERAL  
10% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0021 ST. CLAIR CO.	0021 CLINTON CO.	0021 MARION CO.	CODE NO	ITEM	UNIT		-----	-----	-----
20200100	EARTH EXCAVATION	CU YD	71	16	55								
20400800	FURNISHED EXCAVATION	CU YD	4605	40.5	4559	5.5							
25000210	SEEDING, CLASS 2A	ACRE	3.75	0.13	3.5	0.12							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	338	12	315	11							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	338	12	315	11							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	338	12	315	11							
25000700	AGRICULTURAL GROUND LIMESTONE	TON	7.5	0.1	7.3	0.1							
25100630	EROSION CONTROL BLANKET	SQ YD	17323	240.5	16953	129.5							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4315	60	4218.5	36.5							
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	8875	225	7950	700							
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	325	50	275								
63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	FOOT	2925		2925								
63000370	LONG-SPAN GUARDRAIL OVER CULVERT, 25 FT SPAN	FOOT	525		525								
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	10		8	2							
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4								
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	12		12								
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	86	3	81	2							
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	8		5	3							
63200310	GUARDRAIL REMOVAL	FOOT	14980	472	13524	984							
63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	228	33	195								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	0.2	4.4	0.4							
67100100	MOBILIZATION	L SUM	1	0.1	0.8	0.1							
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.1	0.8	0.1							
78200410	GUARDRAIL MARKERS, TYPE A	EACH	199	5	182	12							
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	94	3	86	5							

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A. RTE.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pwwork\pwwork\conoverpj\20249112\sh...	ts_eng.dgn	DRAWN -	REVISED -			• DB GUARDRAIL UPDATE 2011	VARIOUS	37	4		
PLOT SCALE = 58.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76E78					
PLOT DATE = 3/24/2011		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					