

SUMMARY OF QUANTITIES

90% FED
10% STATE

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	AUXILIARY LANE	RESURFACING
			CONSTRUCTION CODE	0003	0004
20200100	EARTH EXCAVATION	CU YD	545	545	
25000200	SEEDING, CLASS 2	ACRE	0.50	0.50	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	28	28	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	28	28	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	28	28	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.9	1.9	
25100115	MULCH, METHOD 2	ACRE	0.50	0.50	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	93	93	
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3014	3014	
30201500	LIME	TON	60.3	60.3	
31200100	STABILIZED SUBBASE 4"	SQ YD	2153	2153	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	152	152	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.7		2.7
40600300	AGGREGATE (PRIME COAT)	TON	18		18
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1093		1093
40600990	TEMPORARY RAMP	SQ YD	161		161
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	520		520
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	585		585
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	2042	2042	
42101300	PROTECTIVE COAT	SQ YD	2902	2902	
44000100	PAVEMENT REMOVAL	SQ YD	472	472	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	3560		3560
44004250	PAVED SHOULDER REMOVAL	SQ YD	1278	1278	
48100100	AGGREGATE SHOULDERS, TYPE A	TON	185	185	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	35		35
48203100	HOT-MIX ASPHALT SHOULDERS	TON	173		173
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SQ YD	860	860	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4	4	
60107600	PIPE UNDERDRAINS 4"	FOOT	1738	1738	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	127	127	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	62.5	62.5	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
63500310	REMOVE AND REINSTALL DELINEATORS	EACH	7	7	
64200105	SHOULDER RUMBLE STRIPS	FOOT	3156	1738	1418

* DENOTES SPECIALTY ITEM

LAST SAVED = 3/16/2011
PEN TABLE = vb.tbl
PLOT DRIVER = TR-V8pdf-8jback.plt

FILE NAME =	USER NAME = jepettibone	DESIGNED -	REVISED -
\\0906600\0906607\oad\1\plans\0876E94	sht-S00.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/16/2011 8:04:28 AM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**



SUMMARY OF QUANTITIES

SCALE: NONE

SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/70	60-10W,60-10RS-1	MADISON	29	4
CONTRACT NO. 76E94			ILLINOIS FED. AID PROJECT	