

SUMMARY OF QUANTITIES

90% FED.
10% STATE

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	URBAN	AUXILIARY LANE	RESURFACING
			TOTAL QUANTITY		
			CONSTRUCTION CODE	0003	0004
67100100	MOBILIZATION	L SUM	1	0.7	0.3
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2		2
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.5	0.5
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1		1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	120	120	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1448	548	900
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	205		205
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4185	1738	2447
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2105	735	1370
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4602	1542	3060
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	205		205
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2167		2167
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1370		1370
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	280		280
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	8	8	
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1738	1738	
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	735	735	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	88		88
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1019	1019	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	88		88
80300100	LOCATING UNDERGROUND CABLE	FOOT	2038	2038	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
* X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	280		280

* DENOTES SPECIALTY ITEM

LAST SAVED = 3/16/2011
PEN TABLE = vb.tbl
PLOT DRIVER = TR-08.pdf-01ack-up.t