


PIPE UNDERDRAINS						
LOCATION	STATION	SIDE	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	
			FOOT	FOOT	EACH	
I - 55/70 N	1317+05.63 TO 1334+43.89	LT	1738			
	1322+05.63	LT		33	1	
	1327+05.63	LT		45	1	
	1332+05.63	LT		26	1	
	1334+43.89	LT		23	1	
	TOTAL		1738	127	4	

GUARDRAIL									
LOCATION	STATION	SIDE	SPECIAL GUARDRAIL TYPE A, 6 FT POST	TRAFFIC BARRIER TERMINAL		GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED	REMOVE & REINSTALL DELINEATORS	
				TYPE 1 (SPECIAL) TANGENT	TYPE 2				
			FOOT	EACH	EACH	EACH	EACH	EACH	
I - 55/70 N	1317+10	LT						1	
	1317+99	LT						1	
	1318+74	LT						1	
	1319+49	LT						1	
	1320+26	LT						1	
	1321+03	LT						1	
	1321+79	LT						1	
	1321+95 TO 1323+20	LT	62.5	1	1	4	1		
		TOTAL		62.5	1	1	4	1	7

PAVEMENT MARKING																					
LOCATION	STATION	SIDE	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING			WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING			PREFORMED PLASTIC PAVEMENT MARKING, TYPE B	GROOVING FOR RECESSED PAVEMENT MARKING 6"	POLYUREA PAVEMENT MARKING, TYPE 1			PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER			
				LINE				LINE					LINE						LINE		LETTERS & SYMBOLS WHITE
				4 INCH	6 INCH	8 INCH		4 INCH	6 INCH	8 INCH			6 INCH	6 INCH	8 INCH				6 INCH	8 INCH	
			FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	EACH	EACH			
I - 55 N	1263+18.00 TO 1265+48.74	LT	36			152		231		266											
	1263+18.00 TO 1265+82.19	LT	84			260				266											
	1263+18.00 TO 1265+90.00	RT	36		272	172			272												
	1263+18.00 TO 1265+90.00	-	84		70	119				70		70				8	8				
	1263+18.00 TO 1265+90.00	LT	36			217															
I - 55 S	1265+48.74 TO 1265+79.53	LT	12	31		22		31													
I - 55 S	1263+18.00 TO 1270+59.51	RT	96		742	467			742								36	36			
	1263+18.00 TO 1271+50.00	-	252		210	357				210		210					22	22			
	1263+18.00 TO 1271+50.00	LT	108			524			832												
	1266+43.75 TO 1270+59.51	RT	60			337					416						22	22			
	1266+43.75 TO 1270+59.51	RT	60			337					416										
	1270+59.51 TO 1271+45.12	RT	12	86		41		86													
	1270+59.51 TO 1271+47.15	RT	12	88		41		88													
I - 55/70 N	1317+05.63 TO 1334+43.89	LT	72		1738	893			90				1738								
	1317+05.63 TO 1334+43.89	LT	176			349								435							
	1317+05.63 TO 1337+44.04	LT													1019						
	1334+43.89 TO 1337+44.04	LT	300			300								300							
I - 55/70 N	1322+05.63	-															2				
I - 55/70 N	1327+05.63	-															2				
I - 55/70 N	1332+05.63	-															2				
I - 55/70 N	1334+43.89	-															2				
	TOTAL		1448	205	4185	2105	4602	205	2167	1370	280	280	1738	735	8	1019	88	88			

LAST SAVED = 3/16/2011
 PEN TABLE = V6.tbl
 PLOT DRIVER = TR-V6prt Black.plt

FILE NAME =	USER NAME = jepettibone	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SCHEDULES OF QUANTITIES PIPE UNDERDRAIN, GUARDRAIL, AND PAVEMENT MARKING			F.A.I. RTE. = 55/70	SECTION = 60-10W,60-10RS-1	COUNTY = MADISON	TOTAL SHEETS = 29	SHEET NO. = 8	
h:\0906600\0906607\ood\l\plans\0876E94	shh-schedule.dgn	DRAWN -	REVISED -			SCALE: NONE	SHEET NO. 2 OF 2 SHEETS	STA. TO STA.	CONTRACT NO. 76E94					
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -											
	PLOT DATE = 3/16/2011 8:04:32 AM	DATE -	REVISED -											

ILLINOIS FED. AID PROJECT