



F.A.I. ROUTE 255 PROPOSED TYPICAL SECTION ON TANGENT
 CONCRETE 3 LANE SECTION
 VARIOUS LOCATIONS THROUGHOUT PROJECT LIMITS

• MEDIAN SLOPES VARY 1:4 TO 1:8

SB 3 CONCRETE LANES RESURFACING
 STA. 1237+55 TO STA. 1242+08
 STA. 1278+50 TO STA. 1280+00
 STA. 1310+10 TO STA. 1331+86
 STA. 1353+58 TO STA. 1354+99

NB 3 CONCRETE LANES RESURFACING
 STA. 1237+92 TO STA. 1242+36
 STA. 1308+67 TO STA. 1328+97
 STA. 1353+10 TO STA. 1354+50

SB 2 INNER CONCRETE LANES RESURFACING
 STA. 1275+25 TO STA. 1278+50

NB 2 OUTER CONCRETE LANES RESURFACING
 STA. 1246+31 TO STA. 1247+07
 STA. 1284+25 TO STA. 1285+80
 STA. 1295+91 TO STA. 1301+48

SB 1 MIDDLE CONCRETE LANE RESURFACING
 STA. 1280+00 TO STA. 1282+25

NB 1 MIDDLE CONCRETE LANES RESURFACING
 STA. 1285+80 TO STA. 1287+55

SB 2 OUTER CONCRETE LANES RESURFACING
 STA. 1298+70 TO STA. 1301+22

LEGEND

- ① EXISTING FINISHED EMBANKMENT SLOPES
- ② EXISTING STABILIZED SUB-BASE 4"
- ③ EXISTING CRPCC PAVEMENT 10"
- ④ EXISTING PIPE UNDERDRAINS 4"
- ⑤ EXISTING BITUMINOUS SHOULDER 10"
- ⑥ EXISTING AGGREGATE SHOULDER TYPE B
- ⑦ HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4"
- ⑧ PORTLAND CEMENT CONCRETE SURFACE REMOVAL, 2-1/4"
- ⑨ BITUMINOUS MATERIALS (PRIME COAT)
- ⑩ POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90, 2-1/4"

POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90, OVERLAY

FILE NAME = 08378602-SHT06-TYPICAL_WD30.dgn	USER NAME = jbaileyl	DESIGNED - D SOMMER	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED TYPICAL SECTIONS	F.A.I. RTE. 255	SECTION 60-(7, 8) RS-1	COUNTY MADISON	TOTAL SHEETS 29	SHEET NO. 9		
	PLOT SCALE = 6.0000' / IN.	DRAWN - J BAILEY	REVISED -			SCALE:	SHEET NO. 6 OF 6 SHEETS	STA. 1232+26 TO STA. 1354+99	CONTRACT NO. 76E98			
	PLOT DATE = 3/30/2011	CHECKED - T NITTLER	REVISED -			ILLINOIS FED. AID PROJECT						
		DATE - 03/23/11	REVISED -									