

ENTRANCE SCHEDULE

NUMBER	ENTRANCE TYPE	EXIST. SURFACE	EP WIDTH	WIDTH AT 4' OFFSET	ROADWAY AREA	INCIDENTAL HMA SURFACING	BIT. MAT. (PRIME COAT)	AGG. (PRIME COAT)	AGGREGATE WEDGE SHLDRS. TY. B
		FOR INFORMATIONAL PURPOSE ONLY							
		(FT)	(FT)	(SO YD)	(TON)				
52	Private Ent.	Agg.	16.0	12.0	324	31	104	0.49	7
5	Private Ent.	Bit.	16.0	12.0	31	3	3	0.10	
1	Private Ent.	PPC	16.0	12.0	6	1	1	0.10	
8	Comm. Ent.	Agg.	39.0	35.0	132	12	42	0.20	1
2	Comm. Ent.	Bit.	39.0	35.0	33	3	3	0.10	
1	Comm. Ent.	PPC	39.0	35.0	16	1	1	0.02	
SUBTOTALS						51	154.0	1.01	8

SIDE ROADS SCHEDULE

LOCATION	EXIST. SURFACE	EP WIDTH	WIDTH AT 15' OFFSET	ROADWAY AREA	HOT-MIX ASP. SURF. REMOV. - BUTT JT.	INCIDENTAL HMA SURFACING	BIT. MAT. (PRIME COAT)	AGG. (PRIME COAT)			
	FOR INFORMATIONAL PURPOSE ONLY										
	(FT)	(FT)	(SO YD)	(TON)							
FAS 2826 (IL 37)											
Lt.	Rileyville rd.	625+00.00	Oil & Chip	63.0	31.0	105		18	34	0.2	
Rt.	W. Lincoln St.	675+68.80	Oil & Chip	92.0	41.0	153		26	49	0.2	
Rt.	E. Lincoln St.	676+21.60	Oil & Chip	68.0	36.0	113		19	36	0.2	
Lt.	Meadow Ln.	715+28.80	Oil & Chip	78.0	32.0	130		22	42	0.2	
Lt.	Middle Rd.	776+00.80	Oil & Chip	50.0	18.0	83		14	27	0.1	
Rt.	Middle Rd.	776+00.81	Agg.	75.0	31.0	125		21	40	0.2	
Rt.	Beal Rd.	797+65.60	Oil & Chip	76.0	31.0	127		21	41	0.2	
Lt.	Beal Rd.	797+65.61	Oil & Chip	113.0	41.0	188		32	60	0.3	
Lt.	Goshen Meadows	800+82.40	Concrete	70.0	30.0	117	117	10	11	0.2	
Rt.	Sunflower Rd.	832+50.40	Oil & Chip	52.0	24.0	87		15	28	0.1	
Lt.	Violet Rd.	840+42.40	Oil & Chip	73.0	32.0	122		20	39	0.2	
Lt.	Ebenezer Rd.	849+40.00	Oil & Chip	70.0	30.0	117		20	37	0.2	
Lt.	Old Salem Rd	859+43.20	Bit.	86.0	38.0	143	143	12	13	0.2	
PROJECT TOTALS								260	249	457.0	2.50

* FAS 2826
** (109RS-2, 110RS-2, 110-2RS)

FILE NAME =	USER NAME = aybar-js	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ENTRANCES AND SIDE ROADS SCHEDULES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\pv_vork\pmdot\aybar-js\d2256399\bl78185-shr-plan.dgn		DRAWN -	REVISED -			*	**	JEFFERSON	25	9
PLOT SCALE = 100.0164' / IN.		CHECKED -	REVISED -							
PLOT DATE = 3/23/2011		DATE -	REVISED -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____			CONTRACT NO. 78185
ILLINOIS FED. AID PROJECT										