

PAVEMENT MARKING SCHEDULE

STATION TO STATION				PAINT PAVEMENT MARKING			TEMPORARY	SHORT-TERM	NOTES
				4 INCH WHITE (EDGE LINE)	4 INCH YELLOW (NO PASS ZONE OR DBL. YELLOW)	4 INCH (SKIP-DASH)	4 INCH	4 INCH	
				FOOT	FOOT	FOOT	FOOT	FOOT	
MAINLINE: Sta. 559+00 TO Sta. 864+27.79									
	559+00.0	TO	579+53.1	2053.1					
	577+57.5	TO	627+43.1	4985.6					
	625+82.1	TO	864+27.8	23845.7					
LT	559+00.0	TO	572+95.0			349	349	3088	
RT	559+00.0	TO	575+93.0		1,693		1693		NPZ
LT	572+95.0	TO	579+53.1		658		658		NPZ
RT	575+93.0		579+53.1			90	90		
EO. STA. 579+53.1 (BK.) = 577+57.5 (AH.)									
LT	577+57.5	TO	584+96.4		739		739		NPZ
	577+57.5	TO	603+00.0			636	636		
RT	592+98.4	TO	606+01.0		1,303		1303		NPZ
LT	603+00.0	TO	617+93.0		1,493		1493		NPZ
	606+01.0	TO	627+43.1			536	536		
RT	621+93.0	TO	627+43.1		550		550		NPZ
EO. STA. 627+43.1 (BK.) = 625+82.1 (AH.)									
	625+82.1	TO	862+24.0			5,910	5,910		
RT	625+82.1	TO	631+33.2		551		551		NPZ
LT	631+33.2	TO	641+30.2		997		997		NPZ
RT	679+26.0	TO	685+27.0		601		601		NPZ
LT	685+27.0	TO	691+26.0		599		599		NPZ
RT	747+28.0	TO	754+29.0		701		701		NPZ
LT	757+30.0	TO	764+28.0		698		698		NPZ
RT	817+22.0	TO	829+24.0		1,202		1,202		NPZ
LT	829+24.0	TO	838+23.0		899		899		NPZ
RT	853+26.0		862+24.0		898		898		NPZ
LT	862+24.0	TO	864+27.8		204		204		NPZ
RT	862+24.0		864+27.8		204		204		NPZ
SUB-TOTALS MAINLINE				61,769	13,989	7,520	21,510	3,088	
TOTALS					83,278		21,510	3,088	

* FAS 2826
** (109RS-2, 110RS-2, 110-2RS)

FILE NAME =	USER NAME = eybar.js	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A. RTE.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\p\pidot\eybar.js\0256359\bl78185-shr-plan.dgn		DRAWN -	REVISED -			*	**	JEFFERSON	25	10
PLOT SCALE = 100.0164' / IN.		CHECKED -	REVISED -							
PLOT DATE = 3/23/2011		DATE -	REVISED -		SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____					ILLINOIS FED. AID PROJECT CONTRACT NO. 78185