

EARTHWORK SCHEDULE

STRUCTURE NUMBER OF PIER	COUNTY	ROUTE	EARTH EXCAVATION	EMBANKMENT	SHRINKAGE FACTOR	EXCAVATION ADJUSTED FOR SHRINKAGE	EXCESS EXCAVATION	FURNISHED EXCAVATION	COMMENTS
			CU YD	CU YD		CU YD	CU YD	CU YD	
044-0034	JOHNSON	I-24	17.9	555.1	0.42	7.5		547.6	
044-0051	JOHNSON	I-24	210.5	137.8	0.62	131.0		6.7	
064-0029	MASSAC	I-24	9.8	422.1	0.42	4.1		418.0	
077-0027	PULASKI	I-57	103.9	18.2	0.47	48.8	30.5		
077-0033	PULASKI	I-57	5.7	200.7	0.42	2.4		167.8	30.5 CU YD FROM SN 077-0027
077-0032	PULASKI	I-57	144.0	195.7	0.48	69.7		125.9	
091-0046	UNION	I-57	412.8	714.7	0.59	242.2		472.5	
091-0049	UNION	I-57	509.2	413.9	0.64	324.3		89.6	
091-0042	UNION	I-57	528.4	529.8	0.66	346.7		183.1	
100-0060	WILLIAMSON	I-57		490.0	NA			490.0	
100-0053	WILLIAMSON	I-57	117.1	285.9	0.6	67.2		218.7	
100-0059	WILLIAMSON	I-57	14.8	495.9	0.4	6.2		489.8	
100-0039	WILLIAMSON	I-57	400.4	245.7	0.6	256.7	11.0		
100-0044	WILLIAMSON	I-57	487.9	476.4	0.6	308.0		157.4	11 CU YD FROM SN 100-0039
100-0054	WILLIAMSON	I-57	216.8	269.8	0.6	125.1		144.7	
100-0057	WILLIAMSON	I-57	202.9	204.9	0.6	115.0		89.9	
028-0058	FRANKLIN	I-57	244.4	432.6	0.6	144.4		288.2	
TOTALS			3626.3	6089.2				3890.1	

DRAINAGE SCHEDULE

STRUCTURE NUMBER OF PIER	ROUTE	COUNTY	LOCATION		PIPE CULVERTS, CLASS A, TYPE 2 24"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	GRATING FOR CONCRETE FLARED END SECTION 24"	PIPE CULVERT REMOVAL	DELINEATORS
			BEGINNING STATION	ENDING STATION					
091-0042	I-57	UNION	2473+75	2477+80	405	2	2	2	
028-0058	I-57	FRANKLIN	238+00		20	1	4	1	
TOTALS					425	3	3	3	