

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	CONSTRUCTION TYPE CODE	TOTAL QUANTITIES	100% STATE 0021	
		ITEM		MARKET ST AND WASHINGTON ST 100% STATE	MAIN ST AND WASHINGTON ST 100% STATE
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	588	422	166
44000600	SIDEWALK REMOVAL	SQ FT	618	452	166
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5	0.5
72000100	SIGN PANEL, TYPE 1	SQ FT	12	6	6
80300100	LOCATING UNDERGROUND CABLE	FOOT	25	15	10
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	37	37	
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	21	21	
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	134	70	64
81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	72	72	
81400100	HANDHOLE	EACH	3	3	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	58	58	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	955	505	450
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	145	145	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	145	145	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	558	495	63
87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	2	2	
87900200	DRILL EXISTING HANDHOLE	EACH	6	3	3
88500100	INDUCTIVE LOOP DETECTOR	EACH	5	4	1
88600100	DETECTOR LOOP, TYPE 1	FOOT	650	509	141
88800100	PEDESTRIAN PUSH BUTTON	EACH	8	4	4
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	2	1	1

FILE NAME =	USER NAME = poe1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\poe1\0253853\78235-ht-plan.dgn	PLOT SCALE = 1/32" = 1' / IN.	DRAWN -	REVISED -			* 09 CM TRAFFIC SIGNAL 2011-1	HAMILTON	9	3	
PLOT DATE = 3/7/2011	DATE -	CHECKED -	REVISED -			CONTRACT NO. 78235				
						SCALE:	SHEET NO.	OF	SHEETS	STA.