

CODE NO	SUMMARY OF QUANTITIES ITEM	CONSTRUCTION TYPE CODE - 0005								
		UNIT	TOTAL QUANTITIES	FUNDING 100% STATE						
				-JACKSON COUNTY		SALINE COUNTY		JOHNSON COUNTY		WILLIAMSON CO
LOCATION 1 IL 13	LOCATION 2 OLD IL 13	LOCATION 3 IL 13	LOCATION 4 US 45	LOCATION 5 US 45	LOCATION 6 US 45	LOCATION 7 TERMINAL DRIVE				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, (VARIABLE DEPTH)	SQ YD	15645	1,081	667	9,956	2,924	600	417	
20200100	EARTH EXCAVATION	CU YD	18							18
25000115	SEEDING, CLASS 1B	ACRE	0.1							0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12							12
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	12							12
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12							12
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2							0.2
25100115	MULCH, METHOD 2	ACRE	0.1							0.1
25100630	EROSION CONTROL BLANKET	SQ YD	47							47
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10							10
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2480	162	100	1,500	436	90	62	130
40600300	AGGREGATE (PRIME COAT)	TON	2							2
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	221	66		155				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	60							60
40600990	TEMPORARY RAMP	SQ YD	414	33	24	133	133	27	27	37
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	68							68
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	58		58					
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	65							65
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	87					47	40	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	759		45	503	211			
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "D", N105	TON	56	56						
44000100	PAVEMENT REMOVAL	SQ YD	150							150

FILE NAME =	USER NAME = Bradleyf	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw_work\pmdot\bradleyf\02256864\78	3B-sheets.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	09 CM RESURFACING 2011	VARIOUS	64	7
	PLOT SCALE = 51.5915' / IN.	CHECKED -	REVISED -		CONTRACT NO. 78238									
	PLOT DATE = 4/1/2011	DATE -	REVISED -		ILLINOIS FED. AID PROJECT									