

**PAVEMENT AND SHOULDER SCHEDULE**

LOCATION	HOT MIX ASPHALT SURFACE COURSE. MIX "C", N70	HOT MIX ASPHALT SURFACE COURSE. MIX "C", N90	HOT MIX ASPHALT SURFACE COURSE. MIX "D", N90	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE. MIX "D", N105	HOT MIX ASPHALT BINDER COURSE. IL-19.0, N70	HOT MIX ASPHALT BINDER COURSE. IL-19.0, N90	HMA SHOULDERS	HMA SHOULDERS 8"	LEVELING BINDER MACHINE METHOD, N90	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMPORARY RAMP
	TON	TON	TON	TON	TON	TON	TON	SO YD	TON	GAL	TON	SO YD
<b>LOCATION 1 IL 13 WB DEPARTURE OF BIG MUDDY BRIDGE</b>												
STA 342+83.13 TO STA 345+33.13				56			81		66	162		33
<b>LOCATION 2 OLD IL 13</b>												
STA 273+30 TO STA 275+30			45			58	23			100		24.4
<b>LOCATION 3 IL 13 C. MILLS ROAD TO LOVERS LANE</b>												
STA 797+50 TO STA 806+40			199.4				23		23	594		26.6
STA 797+50 TO STA 800+00			56				47		47	174		26.6
STA 848+00 TO STA 851+00			67.6				8		8	200		26.6
STA 916+30 TO STA 920+30			90				48		48	266		26.6
STA 916+30 TO STA 920+30			90				29		29	266		26.6
<b>LOCATION 4 US 45 HARRISBURG TO C. MILLS</b>												
STA 52+60 TO STA 54+40			40.3				22			84		26.6
STA 160+70 TO STA 162+60			42.6				47			88		26.6
STA 164+90 TO STA 166+80			42.6				22			88		26.6
STA 233+50 TO STA 235+40			42.6				29			88		26.6
STA 239+70 TO STA 241+60			42.6				11			88		26.6
<b>LOCATION 5 US 45 BIKE TRAIL</b>												
STA 1567+20 TO STA 1569+00		40.3					16			90		26.6
<b>LOCATION 6 US 45 BIKE TRAIL</b>												
STA 148+50 TO STA 150+60		47					9			62		26.6
<b>LOCATION 7 TERMINAL DRIVE</b>												
STA 1+31												23
STA 1+31 TO STA 2+60					68							
STA 1+31 TO STA 3+41	65							241		130	2	
STA 3+41												14
<b>TOTALS</b>	<b>65</b>	<b>87</b>	<b>759</b>	<b>56</b>	<b>68</b>	<b>58</b>	<b>415</b>	<b>241</b>	<b>221</b>	<b>2480</b>	<b>2</b>	<b>414</b>

FILE NAME =	USER NAME = Brodeyrf	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\brodeyrf\d0256064\78238-sheets.dgn	DRAWN -	REVISED -	09 CM RESURFACING 2011			VARIOUS	64	15			
PLOT SCALE = 51.5915' / IN.	CHECKED -	REVISED -	<b>CONTRACT NO. 78238</b>								
PLOT DATE = 4/1/2011	DATE -	REVISED -	<b>ILLINOIS FED. AID PROJECT</b>								
						SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.