

**SUMMARY OF QUANTITIES**  
CONSTRUCTION TYPE CODE: 0011

PAY CODE	QUANTITY	UNIT	ITEM
20100110	326	Unit	Tree Removal (6 to 15 units diameter)
20100210	342	Unit	Tree Removal (over 15 units diameter)
*20200100	389	Cu. Yd.	Earth Excavation
20300100	115	Cu. Yd.	Channel Excavation
20400800	233	Cu. Yd.	Furnished Excavation
25100630	2,814	Sq. Yd.	Erosion Control Blanket
*28000305	87	Foot	Temporary Ditch Checks
28000400	559	Foot	Perimeter Erosion Barrier
*31100100	857	Ton	Subbase Granular Material, Type A
*40200800	25	Ton	Aggregate Surface Course, Type B
*40600100	616	Gallon	Bituminous Materials (Prime Coat)
40603305	204	Ton	Hot-Mix Asphalt Surface Course, Mix "C", N30
48101200	111	Ton	Aggregate Shoulders, Type B
*50100100	1	Each	Removal of Existing Structures
50105220	21	Foot	Pipe Culvert Removal
50300225	45.8	Cu. Yd.	Concrete Structures
50300280	4.2	Cu. Yd.	Concrete Encasement
50400605	2,036	Sq. Ft.	Precast Prestressed Concrete Deck Beams (33" Depth)
50800105	5,480	Pound	Reinforcement Bars
+ 50900205	173	Foot	Steel Railing, Type S1
51201610	260	Foot	Furnishing Steel Piles HP12x63
51202305	260	Foot	Driving Piles
51203610	2	Each	Test Pile Steel HP12x63
51500100	1	Each	Name Plates
*60107700	1,059	Foot	Pipe Underdrains 6"
+ 63000001	50	Foot	Steel Plate Beam Guardrail, Type A, 6 Foot Posts
+ 63100075	4	Each	Traffic Barrier Terminal, Type 5A
+*63100167	4	Each	Traffic Barrier Terminal, Type 1 (Special) Tangent
67100100	1	L. Sum	Mobilization
+ 78200410	12	Each	Guardrail Markers, Type A
Z0013798	1	L. Sum	Construction Layout
*X2070302	100	Ton	Porous Granular Embankment, Special
*X2501100	0.59	Acre	Seeding, Class 3 (Special)
*X2810212	909	Ton	Stone Riprap, Class A6 (Special)
*X7010216	1	L. Sum	Traffic Control and Protection, (Special)

\*See BLR 11310 in the contract documents for Special Provisions.

+Specialty Item

FILE NAME = S:\PROJECTS\2010\1285D10\_BureauCo\_TR240\DESIGN\STRUCT\1285D10\_SummaryOfQuantities.dgn

USER NAME =	DESIGNED - B.S.K.	REVISED -
	CHECKED - B.K.C.	REVISED -
PLOT SCALE =	DRAWN - R.D.A.	REVISED -
PLOT DATE =	CHECKED - B.S.K.	REVISED -

**BUREAU COUNTY**  
**TR 240 OVER PLOW HOLLOW CREEK**  
**STATION 15 + 00**

**SUMMARY OF QUANTITIES**  
**STRUCTURE NO. 006-4012**

STA. 12+00 TO STA. 18+00

TWP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
240	10-01121-00-BR	BUREAU	23	2
WHA# 1285D10		CONTRACT NO. 87483		
[ILLINOIS] FED. AID PROJECT BROS-0011(075)				