

## SUMMARY OF QUANTITIES

	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
					RECONSTRUCTION, CAPACITY ADDED 0003	SAFETY (TRAFFIC SIGNALS) 0021
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	20	20	-
#	20101000	TEMPORARY FENCE	FOOT	210	210	-
	20101100	TREE TRUNK PROTECTION	EACH	10	10	-
	20200100	EARTH EXCAVATION	CU YD	688	688	-
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	764	764	-
#	20400800	FURNISHED EXCAVATION	CU YD	1,322	1,322	-
	20800150	TRENCH BACKFILL	CU YD	102	102	-
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7,511	7,511	-
	25000200	SEEDING, CLASS 2	ACRE	1.58	1.58	-
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	144	144	-
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	144	144	-
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	144	144	-
	25100630	EROSION CONTROL BLANKET	SQ YD	7,511	7,511	-
	25200200	SUPPLEMENTAL WATERING	UNIT	48	48	-
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	158	158	-
	28000305	TEMPORARY DITCH CHECKS	FOOT	350	350	-
	28000400	PERIMETER EROSION BARRIER	FOOT	920	920	-
	28000510	INLET FILTERS	EACH	4	4	-
#	25100115	MULCH, METHOD 2	ACRE	1.58	1.58	-
	28100107	STONE RIPRAP, CLASS A4	SQ YD	28	28	-
	28200200	FILTER FABRIC	SQ YD	28	28	-
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	346	346	-
#	35800100	PREPARATION OF BASE	SQ YD	427	427	-
	35800200	AGGREGATE BASE REPAIR	TON	25	25	-
#	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	9	-
#	40600300	AGGREGATE (PRIME COAT)	TON	37	37	-
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	2	2	-
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	822	822	-
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,070	2,070	-
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	493	493	-

# INDICATES SPECIAL PROVISION  
\* INDICATES SPECIALTY ITEM

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC. ...  
 SURVEYING, ENGINEERING, ARCHITECTURE & PLANNING  
 1100 N. WASHINGTON ST., SUITE 200, DEKALB COUNTY, IL 62521  
 PHONE: 618-233-1234 FAX: 618-233-1234  
 WWW.BAXTERANDWOODMAN.COM



DESIGNED - DJS	REVISED - 4-14-11 PER CITY REVIEW
DRAWN - UKB	REVISED -
CHECKED - RWL	REVISED -
DATE - 04-01-2011	FILE NAME - 081068-41-QNTY.dgn

**CITY OF DeKALB, ILLINOIS  
PEACE ROAD  
IMPROVEMENTS**

**SUMMARY OF QUANTITIES**

SCALE: \_\_\_\_\_ STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-01-WR	DeKALB	33	4
CONTRACT NO. 87488				
FED. ROAD DIST. NO. 3 [ILLINOIS] FED. AID PROJECT M-50170451				