

SUMMARY OF QUANTITIES

	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
					RECONSTRUCTION, CAPACITY ADDED 0003	SAFETY (TRAFFIC SIGNALS) 0021
#	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,923	3,923	-
#	72000100	SIGN PANEL - TYPE 1	SQ FT	37	37	-
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	3	3	-
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	75	75	-
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,818	3,818	-
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	34	34	-
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,148	1,148	-
*	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1,276	1,276	-
*	78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	65	65	-
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	-
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	-
#	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,709	1,709	-
*	81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	120	-	120
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	308	-	308
*#	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2	-	2
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	308	-	308
*	87900200	DRILL EXISTING HANDHOLE	EACH	1	-	1
*	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	308	-	308
*#	89502380	REMOVE EXISTING HANDHOLE	EACH	1	-	1
*#	Z0000500	ADJUSTING EXISTING HANDHOLE	EACH	3	-	3
#	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	1,525	1,525	-
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-
#	Z0019600	DUST CONTROL WATERING	UNIT	100	100	-
#	Z0021900	EXPANSION JOINT REPAIR	FOOT	32	32	-
#	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	130	130	-
#	Z0062456	TEMPORARY PAVEMENT	SQ YD	420	420	-
			—	—	—	-
#	XX005472	DRAINAGE STRUCTURE SPECIAL	EACH	2	2	-
*#	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	-

INDICATES SPECIAL PROVISION Δ ∅∅42
 * INDICATES SPECIALTY ITEM

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC. ... \projects\new\10723\14.dwg
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 061-123456789 EXP. 12/31/2011
 7/11/2011 9:59:03 AM I:\projects\10723\14.dwg



DESIGNED -	DJS	REVISED -	-4-14-11 PER CITY REVIEW
DRAWN -	UKB	REVISED -	
CHECKED -	RWL	REVISED -	
DATE -	04-01-2011	FILE NAME -	081068-41-ONTY.dgn

CITY OF DeKALB, ILLINOIS PEACE ROAD IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-01-WR	DeKALB	33	6
CONTRACT NO. 87488				
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT M-50170451				