

CONCRETE SCHEDULE					
LOCATION	AGGREGATE BASE COURSE, TYPE B 4" (SQ YD)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FOOT)	CLASS SI CONCRETE (OUTLET) (CU YD)	REINFORCEMENT BARS (POUND)	PROTECTIVE COAT (SQ YD)
PEACE ROAD					
STA 114+50 TO STA 115+35	-	-	-	-	-
STA 115+35 TO STA 116+00	-	-	-	-	-
STA 116+00 TO STA 117+50	52	150	-	-	43
STA 117+50 TO STA 123+00	189	550	-	334	158
STA 123+00 TO STA 124+52	105	304	3.5	14	88
TOTAL	346	1,004	3.5	348	289

SIGNING SCHEDULE						
TYPE	DESCRIPTION	SIZE	LOCATION	SIGN PANEL TYPE 1 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY TYPE A (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FT)
R2-1	Speed Limit (45 mph)	30" x 36"	116+25, 22' LT	8	-	15
R2-2	Speed Limit (45 mph)	30" x 36"	116+25, 22' LT	-	1	-
W3-3	Signal Ahead	30" x 30"	118+89, 22' LT	7	-	15
W3-4	Signal Ahead	30" x 30"	121+48, 26' LT	-	1	-
W4-2R	Lane Ends	36" x 36"	123+30, 29' LT	9	-	15
W54-56	Plant Entrance Ahead	30" x 30"	124+47, 28' LT	7	-	15
W54-57	Plant Entrance Ahead	30" x 30"	124+47, 29' LT	-	1	-
W9-1R	Right Lane Ends	30" x 30"	131+05, 30' LT	7	-	15
TOTAL				38	3	75

ROADWAY REMOVAL SCHEDULE				
LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	PAVEMENT REMOVAL (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, 4 3/4" (SQ YD)	GUARDRAIL REMOVAL (FOOT)
PEACE ROAD				
STA 114+50 TO STA 115+35	115	6	609	-
STA 115+35 TO STA 116+00	131	8	-	-
STA 116+00 TO STA 117+50	-	17	-	-
STA 117+50 TO STA 123+00	-	62	-	-
STA 121+52 TO STA 124+52, LT	-	-	-	300
STA 121+30 TO STA 124+30, RT	-	-	-	300
STA 123+00 TO STA 124+52	576	858	-	-
TOTAL	822	951	609	600

GUARD RAIL AND TRAFFIC BARRIER TERMINAL SCHEDULE						
LOCATION	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 2 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) (EACH)	GUARDRAIL MARKERS, TYPE A (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)
PEACE ROAD						
STA 119+73.75, 20' RT TO STA 120+23.75, 20' RT	-	-	-	1	-	1
STA 120+23.75, 20' RT TO STA 123+86.25, 28' RT	362.5	-	-	-	4	-
STA 123+86.25, 28' RT TO STA 124+30, 26' RT	-	-	1	-	-	-
STA 120+59.25, 21' LT TO STA 120+71.75, 22' LT	-	1	-	-	-	1
STA 120+71.75, 22' LT TO STA 124+09.25, 27' LT	337.5	-	-	-	4	-
STA 124+09.25, 27' LT TO STA 124+53, 26' LT	-	-	1	-	-	-
TOTAL	700	1	2	1	8	2

TEMPORARY PAVEMENT MARKING SCHEDULE						
	PAVEMENT MARKING REMOVAL (SQ FT)	SHORT-TERM PAVEMENT MARKING (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 4" (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 8" (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 12" (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
TOTAL FROM STAGE 1 & 2	-	-	630	-	-	126
TOTAL FROM STAGE 3	1,709	-	4,805	10	-	965
TOTAL FROM STAGE 4	-	-	4,935	10	-	991
TOTAL FROM STAGE 5	-	401	5,094	34	1,213	1,841
TOTAL	1,709	401	15,464	54	1,213	3,923

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL ENGINEERING
 LICENSE NO. - 184-00021 - EXPIRES 4/30/2011
 744630 AM 7/14/2011



DESIGNED - DJS
 DRAWN - UKB
 CHECKED - RWL
 DATE - 04-01-2011
 REVISED -4-14-11 PER CITY REVIEW
 REVISED -
 REVISED -
 FILE NAME - 081068-41-SCHEDULE-QNTY.dgn

CITY OF DeKALB , ILLINOIS
PEACE ROAD
IMPROVEMENTS

SCHEDULE OF MATERIALS

SCALE: STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-01-WR	DeKALB	33	11
CONTRACT NO. 87488				
FED. ROAD DIST. NO. 3 [ILLINOIS] FED. AID PROJECT M-5017(045)				