

SUMMARY OF QUANTITIES WEST EVERGREEN AVENUE						
ITEM NO.	PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% LOCAL	100% LOCAL
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	145	104	41
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	235	107	128
3	20100500	TREE REMOVAL ACRES	ACRE	6.85	6.7	0.15
4	20200100	EARTH EXCAVATION	CU YD	58302	56350	1952
5	20400800	FURNISHED EXCAVATION	CU YD	15702	15702	0
6	20700110	POROUS GRANULAR EMBANKMENT	TON	125	0	125
7	20800150	TRENCH BACKFILL	CU YD	262	229	33
8	28000305	TEMPORARY DITCH CHECKS	FOOT	2212	2212	0
9	28000400	PERIMETER EROSION BARRIER	FOOT	1657	1292	365
10	28000500	INLET AND PIPE PROTECTION	EACH	36	30	6
11	28000510	INLET FILTERS	EACH	25	19	6
12	28100809	STONE DUMPED RIPRAP, CLASS A5	TON	765	765	0
13	28200200	FILTER FABRIC	SQ YD	2708	2569	139
14	28400100	GABIONS	CU YD	478	177	301
15	28400700	SLOPE MATTRESS 9"	SQ YD	86	86	0
16	31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	400	0	400
17	35100100	AGGREGATE BASE COURSE, TYPE A	TON	3850	3769	81
18	35200410	PROCESSING SOIL-CEMENT BASE COURSE 10"	SQ YD	18432	18432	0
19	35200500	CEMENT	100 WT	15593	15593	0
20	40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	7483	7401	82
21	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2552	2552	0
22	40600300	AGGREGATE (PRIME COAT)	TON	51	51	0
23	40603005	HOT-MIX ASPHALT BINDER COURSE, IL-11.0, N70	TON	3739	3739	0
24	40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	2564	2564	0
25	40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	729	634	95
26	40800030	AGGREGATE (PRIME COAT)	TON	5	4.4	0.6
27	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	207	173	34
28	42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	1350	0	1350
29	42001300	PROTECTIVE COAT	SQ YD	4225	1935	2290
30	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	6364	0	6364
31	42400800	DETECTABLE WARNINGS	SQ FT	10	0	10
32	44000600	SIDEWALK REMOVAL	SQ FT	1100	0	1100
33	50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	0
34	50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1	0
35	50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1	0
36	50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1	0
37	50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	0	1
38	50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1	0	1
39	50105220	PIPE CULVERT REMOVAL	FOOT	282	250	32
40	50200100	STRUCTURE EXCAVATION	CU YD	166	166	0
41	50300225	CONCRETE STRUCTURES	CU YD	68.9	68.9	0
42	50300280	CONCRETE ENCASEMENT	CU YD	4.2	4.2	0
43	50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	3562	3562	0
44	50800105	REINFORCEMENT BARS	POUND	5790	5790	0
45	50901050	STEEL RAILING, TYPE SM	FOOT	216	216	0
46	51201400	FURNISHING STEEL PILES HP10X42	FOOT	1242	1242	0
47	51202305	DRIVING PILES	FOOT	1242	1242	0
48	51203400	TEST PILE STEEL HP10X42	EACH	3	3	0
49	51500100	NAME PLATES	EACH	1	1	0
50	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	0	1
51	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4	0
52	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	0
53	54213717	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 72"	EACH	1	1	0
54	54214089	ALUMINUM END SECTIONS 24"	EACH	10	10	0
55	54214095	ALUMINUM END SECTIONS 30"	EACH	2	2	0
56	54214101	ALUMINUM END SECTIONS 36"	EACH	2	2	0
57	54217680	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 24" RISER	EACH	1	1	0
58	542C1069	PIPE CULVERTS, CLASS C, TYPE 2 24"	FOOT	295	295	0
59	542C1075	PIPE CULVERTS, CLASS C, TYPE 2 30"	FOOT	80	80	0
60	542C1081	PIPE CULVERTS, CLASS C, TYPE 2 36"	FOOT	80	80	0
61	550A2520	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 2 12"	FOOT	851	558	93
62	550A2530	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 2 15"	FOOT	829	472	157
63	550A2540	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 2 18"	FOOT	837	804	33
64	550A2560	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 2 24"	FOOT	694	694	0
65	550A2600	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 2 36"	FOOT	102	102	0
66	550A2860	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 3 72"	FOOT	95	95	0
67	56100050	DUCTILE IRON WATER MAIN TEE, 12" X 6"	EACH	1	0	1
68	56100600	WATER MAIN 6"	FOOT	4	0	4
69	56100900	WATER MAIN 12"	FOOT	751	0	751

Δ Revised 5-31-2011

SUMMARY OF QUANTITIES WEST EVERGREEN AVENUE						
ITEM NO.	PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% LOCAL	100% LOCAL
70	56104900	WATER VALVES 6"	EACH	1	0	1
71	56109100	TAPPING VALVES AND SLEEVES 12"	EACH	2	0	2
72	56109404	DUCTILE IRON WATER MAIN FITTINGS 12" 11.25 DEGREE BEND	EACH	2	0	2
73	56109412	DUCTILE IRON WATER MAIN FITTINGS 12" 22.50 DEGREE BEND	EACH	2	0	2
74	56109438	DUCTILE IRON WATER MAIN FITTINGS 12" 90.00 DEGREE BEND	EACH	1	0	1
75	56400600	FIRE HYDRANTS	EACH	1	0	1
76	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	15	14	1
77	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0
78	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0
79	60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4	1	3
80	60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	1	0	1
81	60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	0	1
82	60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	0	1
83	60240303	INLETS, TYPE B, TYPE 9 FRAME AND GRATE	EACH	1	0	1
84	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	25	25	0
85	60603450	GUTTER INLET (SPECIAL)	EACH	3	3	0
86	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3532	2908.5	623.5
87	63000015	STEEL PLATE BEAM GUARDRAIL, TYPE D	FOOT	100	100	0
88	63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	2	2	0
89	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	0
90	63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	138	0	138
91	63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	2	0	2
92	67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	24	24	0
93	67100100	MOBILIZATION	LUMP SUM	1	1	0
94	70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	LUMP SUM	1	1	0
95	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LUMP SUM	1	1	0
96	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	16105	15101	1004
97	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	26	26	0
98	78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	0
99	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	0
100	K1005418	TEMPORARY SEEDING	ACRE	18.5	17.5	1
101	X0325592	REMOVE AND REPLACE STONE RIPRAP	SQ YD	1778	1778	0
102	X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	18.5	17.5	1
103	X6022230	MANHOLES, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1	0
104	X6023212	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE, SPECIAL	EACH	1	1	0
105	X6023508	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	16	16	0
106	X6063000	CONCRETE GUTTER, TYPE B (SPECIAL)	FOOT	1381	1381	0
107	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LUMP SUM	1	1	0
108	Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	4	0	4
109	Z0018900	DRILL AND GROUT DOWEL BARS	EACH	34	0	34
110	Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER	EACH	25	19	6
111	Z0077002	CLEANING	FOOT	1382	0	1382
112	XX000610	WATER MAIN REMOVAL	FOOT	10	8	2
113	XX005776	RELOCATE EXISTING MAILBOX	EACH	1	0	1
114	XX006571	DUCTILE IRON WATER MAIN FITTINGS 12" 45.00 DEGREE BEND	EACH	1	0	1
115	XX007717	REMOVE AND REPLACE BOLLARDS	EACH	3	0	3
		" PLUG	EACH	2	0	2

Δ SPECIALTY ITEMS