



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2011

SUBJECT: FAU Route 9148  
(Milburn School Road)  
Project M-5011(261)  
Section 06-00059-00-PV & 08-00059-01-PV (O'Fallon)  
St. Clair County  
Contract No 97447  
Item 266 A  
June 17, 2011 Letting

TO PROSPECTIVE BIDDERS:

To clarify information it is necessary to revise the following:

**Proposal-Revised pages 1, 2, 5, and 6 of the Schedule of Prices and page 11 of the Special Provisions.**

**Plans- Revised sheets 3, 6-9, 20, 27, 40, 52 and 53**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Scott Stitt  
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger', followed by the letters 'P.E.' in a smaller font.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

STATE JOB #- C-98-321-09  
 PPS NBR - 8-10314-0000

COUNTY NAME	CODE	DIST	SECTION NUMBER	PROJECT NUMBER	ROUTE
ST CLAIR	163	08	06-00059-00-PV 08-00059-01-PV	M-5011/261/000	FAU 9148

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
XX008481	REM & RELAY SS 18	FOOT	44.000 X	=			
X0976500	END SECTIONS REMOVED	EACH	3.000 X	=			
X5427600	REM & RELOC END SECT	EACH	2.000 X	=			
X6024242	INLETS SPL N1	EACH	7.000 X	=			
X6024244	INLETS SPL N2	EACH	2.000 X	=			
X6024246	INLETS SPL N3	EACH	38.000 X	=			
X6024248	INLETS SPL N4	EACH	6.000 X	=			
X7010216	TRAF CONT & PROT SPL	L SUM	1.000 X	=			
X7800100	PT PVT MK- RAISED MED	SQ FT	342.000 X	=			
Z0022800	FENCE REMOVAL	FOOT	419.000 X	=			
Z0056608	STORM SEW WM REQ 12	FOOT	349.000 X	=			
Z0056610	STORM SEW WM REQ 15	FOOT	283.000 X	=			
Z0056612	STORM SEW WM REQ 18	FOOT	295.000 X	=			
Z0056616	STORM SEW WM REQ 24	FOOT	33.000 X	=			
Z0056624	STORM SEW WM REQ 42	FOOT	101.000 X	=			

revised 6/1/11

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
Z0076600	TRAINEES	HOUR	500.000 X	0.80	=	400.00	
20100110	TREE REMOV 6-15	UNIT	59.000 X		=		
20100210	TREE REMOV OVER 15	UNIT	28.000 X		=		
20200100	EARTH EXCAVATION	CU YD	5,186.000 X		=		
20201200	REM & DISP UNS MATL	CU YD	3,487.000 X		=		
20400800	FURNISHED EXCAVATION	CU YD	1,843.000 X		=		
20800150	TRENCH BACKFILL	CU YD	1,739.000 X		=		
25000100	SEEDING CL 1	ACRE	2.000 X		=		
25000400	NITROGEN FERT NUTR	POUND	189.000 X		=		
25000500	PHOSPHORUS FERT NUTR	POUND	189.000 X		=		
25000600	POTASSIUM FERT NUTR	POUND	189.000 X		=		
25100115	MULCH METHOD 2	ACRE	2.000 X		=		
28000250	TEMP EROS CONTR SEED	POUND	209.000 X		=		
28000305	TEMP DITCH CHECKS	FOOT	20.000 X		=		
28000400	PERIMETER EROS BAR	FOOT	3,860.000 X		=		

revised 6/1/11

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
542D0215	P CUL CL D 1 10	FOOT	20.000 X	=		=	
542D0220	P CUL CL D 1 15	FOOT	55.000 X	=		=	
54213663	PRC FLAR END SEC 18	EACH	1.000 X	=		=	
54213669	PRC FLAR END SEC 24	EACH	2.000 X	=		=	
54213675	PRC FLAR END SEC 30	EACH	1.000 X	=		=	
54213687	PRC FLAR END SEC 42	EACH	1.000 X	=		=	
550A2320	SS RG CL A 1 12	FOOT	733.000 X	=		=	
550A2330	SS RG CL A 1 15	FOOT	675.000 X	=		=	
550A2340	SS RG CL A 1 18	FOOT	518.000 X	=		=	
550A2360	SS RG CL A 1 24	FOOT	413.000 X	=		=	
550A2380	SS RG CL A 1 30	FOOT	12.000 X	=		=	
550A2400	SS RG CL A 1 36	FOOT	54.000 X	=		=	
550A2520	SS RG CL A 2 12	FOOT	554.000 X	=		=	
550A2530	SS RG CL A 2 15	FOOT	1,329.000 X	=		=	
550A2540	SS RG CL A 2 18	FOOT	396.000 X	=		=	

revised 6/1/11

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
550A2560	SS RG CL A 2 24	FOOT	260.000 X	=			
55100500	STORM SEWER REM 12	FOOT	36.000 X	=			
55100700	STORM SEWER REM 15	FOOT	385.000 X	=			
55101200	STORM SEWER REM 24	FOOT	98.000 X	=			
55101600	STORM SEWER REM 36	FOOT	32.000 X	=			
55101800	STORM SEWER REM 42	FOOT	64.000 X	=			
56109210	WATER VALVES ADJUST	EACH	4.000 X	=			
60218500	MAN TA 4 DIA T3F&G	EACH	1.000 X	=			
60219540	MAN TA 4 DIA T24F&G	EACH	5.000 X	=			
60221000	MAN TA 5 DIA T1F OL	EACH	1.000 X	=			
60221100	MAN TA 5 DIA T1F CL	EACH	1.000 X	=			
60222240	MAN TA 5 DIA T24F&G	EACH	4.000 X	=			
60224039	MAN TA 6 DIA T24F&G	EACH	2.000 X	=			
60235700	INLETS TA T3F&G	EACH	2.000 X	=			
60236200	INLETS TA T8G	EACH	1.000 X	=			

revised 6/1/11

**EROSION CONTROL:** This item of work shall consist of furnishing all labor, equipment and materials necessary to provide erosion control according to details as shown in the plans.

Temporary Seeding shall be utilized when work in highly erodible areas is completed and the permanent seeding cannot be completed in a reasonable time. This work shall also include the cost of placing temporary mulch, Method 1 according to Section 251 of the Standard Specifications and no additional compensation will be allowed.

Perimeter silt fence shall be placed along the toe of fill slopes along the project length prior to constructing the fill.

Inlet and pipe protection shall be installed at the upstream end of each proposed inlet and pipe after each has been installed accordingly to the details as shown in the plans.

Upon completion of each phase of the project, the contractor shall seed and mulch the disturbed areas according to the plans and specifications.

This work shall be done according to Section 280 of the Standard Specifications and the Illinois Environmental Protection Agency's Standards and Specifications for Soil Erosion and Sediment Control, current edition.

This work will be paid for at the contract unit price per pound for TEMPORARY EROSION CONTROL SEEDING, per each for INLET AND PIPE PROTECTION, per foot for PERIMETER EROSION BARRIER, per acre for SEEDING CLASS 1 and per acre for MULCH METHOD 2.

**PAINT PAVEMENT MARKING – RAISED MEDIAN:** Paint pavement marking of the raised medians shall be according to the applicable portions of Section 780 and as specified herein. Median noses and the faces and tops of all mountable curb (modified) shall be painted solid yellow and/or white as shown in the Plans. No spacing will be required for the curb painting. This work will be paid for at the contract unit price per square foot for PAINT PAVEMENT MARKING – RAISED MEDIAN.

**END SECTIONS TO BE REMOVED:** This work shall consist of removing drainage end sections of various materials according to the applicable portions of Section 501 at locations shown in the plans. Work will be paid for at the contract unit price per each for END SECTIONS TO BE REMOVED.

**COMPLETION DATE:** The Contractor shall complete all work by December 1, 2012. The Contractor shall schedule work such that no portion of the roadway is closed to thru traffic over the winter shutdown period.