

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9266	06-0062-06-PV	ST. CLAIR	80	14
FHWA REG. NO. 7	ILLINOIS	PROJECT NO.	RS-0163(035)	
FEDERAL AID PROJECT	CONTRACT NO.		97457	

MISCELLANEOUS SCHEDULES

STORM SEWER PIPE															
FROM	TO	UPSTREAM INVERT	DOWNSTREAM INVERT	STORM SEW CL A 2 12	STORM SEW CL A 2 15	STORM SEW CL A 2 18	STORM SEW CL A 2 21	STORM SEW CL A 2 24	STORM SEW CL A 2 27	STORM SEW CL A 2 30	STORM SEW CL A 2 36	STORM SEW CL A 2 42	STORM SEW CL A 2 36	TRENCH BACKFILL	SLOPE
(FOOT)															
(C.Y.)															

SHILOH CUT-OFF															
1-3	OATS 1-2	544.71	543.64								123			107	0.87%
1-4	1-3	549.71	549.29	28										6	1.50%
1-5	1-3	548.61	547.71								100			92	0.90%
1-28	1-5	551.90	551.39								65			18	0.78%
1-29	1-28	555.58	555.30			29								30	0.97%
1-6	1-28	555.35	554.93					45						30	0.93%
1-7	1-6	558.52	557.68	28										5	3.00%
1-8	1-6	558.67	557.27					140						142	1.00%
1-9	1-8	566.27	565.85	28										4	1.50%
1-10	1-8	566.02	565.02						100					89	1.00%
1-11	1-10	571.88	571.60	28										6	1.00%
1-12	1-10	571.05	570.75			18								21	1.67%
1-13	1-10	574.38	571.38			150								124	2.00%
1-14	1-13	580.30	580.02	28										6	1.00%
1-15	1-13	581.80	579.80			100								72	2.00%
1-16	1-15	587.91	585.41			125								95	2.00%
1-17	1-16	592.92	592.64	28										6	1.00%
1-18	1-16	595.42	592.67		110									70	2.50%
1-19	1-18	599.09	598.81	28										6	1.00%
1-20	1-18	601.72	598.84		96									35	3.00%
1-21	1-20	606.58	604.54	68										19	3.00%
1-22	1-21	608.35	608.07	28										6	1.00%
1-23	1-21	610.60	608.35	50										11	4.50%
1-24	1-23	613.10	610.99	50										10	4.22%
1-25	1-24	614.38	613.10	50										11	2.56%
1-26	1-25	614.66	614.38	28										6	1.00%
1-27	1-26	616.30	614.66	50										9	3.28%
2-29	2-27	592.57	592.49						23					35	0.35%
2-1	2-29	599.80	599.63							33				76	0.52%
2-2	2-1	609.35	609.20				28							36	0.54%
2-28	2-2	610.93	610.40				25							15	2.12%
2-3	2-4	612.48	612.18	30										24	1.00%
2-4	2-1	612.18	611.65			53								44	1.00%
2-5	2-6	622.13	621.65	28										7	1.71%
2-6	2-33	621.65	621.49		8									2	2.00%
2-7	2-6	624.10	621.65		75									23	3.27%
2-8	2-7	629.58	625.83	125										45	3.00%
2-9	2-8	632.64	632.50	28										5	0.50%
2-30	2-9	632.86	632.74	13										3	0.92%
2-10	2-8	635.84	632.64	80										21	4.00%
2-11	2-10	640.60	637.00	90										23	4.00%
2-31	2-11	640.85	640.60	28										9	0.89%
2-12	2-11	644.45	641.90	51										11	5.00%
2-13	2-1	607.71	607.40			63								91	0.49%
2-14	2-13	613.79	613.18	28										7	2.18%
2-15	2-13	607.92	607.71			41								56	0.51%
2-16	2-15	608.00	607.92			17								23	0.47%
2-17	2-16	612.38	612.23			30								11	0.50%
2-18	2-17	613.00	612.88	24										8	0.50%
2-19	2-17	613.00	612.23		24									7	3.21%
2-32	2-22	614.55	614.39	33										6	0.48%
2-33	2-34	620.08	612.34		248									176	3.12%
2-34	2-4	612.34	612.18		8									7	2.00%
SUBTOTAL				1,078	569	626	0	0	240	98	288	23	33	1,807	

SEE ADJACENT TABLE FOR CONTINUED SCHEDULE AND TOTALS

STORM SEWER PIPE (CONT.)															
FROM	TO	UPSTREAM INVERT	DOWNSTREAM INVERT	STORM SEW CL A 2 12	STORM SEW CL A 2 15	STORM SEW CL A 2 18	STORM SEW CL A 2 21	STORM SEW CL A 2 24	STORM SEW CL A 2 27	STORM SEW CL A 2 30	STORM SEW CL A 2 36	STORM SEW CL A 2 42	STORM SEW CL A 2 36	TRENCH BACKFILL	SLOPE
(FOOT)															
(C.Y.)															

SHILOH CUT-OFF (CONT.)															
2-20	2-19	613.11	612.92								15			4	1.27%
2-21	2-20	613.75	613.11								50			14	1.28%
2-22	2-21	614.39	614.00	28										6	1.39%
2-23	2-21	614.63	614.00	60										14	1.05%
2-24	2-23	614.96	614.63	28										6	1.18%
2-25	2-23	615.20	614.63	65										15	0.88%
2-26	2-25	615.59	615.20	28										6	1.39%
3-5	3-1	515.96	515.67								44			16	0.66%
3-2	3-5	516.58	516.06								68			45	0.76%
3-3	3-2	517.94	516.68								198			65	0.64%
3-4	3-3	520.00	518.44					292						103	0.53%
4-2	4-1	515.40	515.06	103										12	0.33%
5-3	5-2	513.77	513.39						96					14	0.40%
5-4	5-2	513.92	513.39						47					7	1.13%
6-2	6-1	529.30	529.12	58										6	0.31%
6-4	6-2	530.75	529.40	125										12	1.08%
7-2	7-1	513.95	513.87					27						5	0.30%
7-3	7-2	514.53	514.05					96						8	0.50%
7-4	7-3	515.43	514.63					160						25	0.50%
7-5	7-4	515.90	515.53					90						21	0.41%
7-6	7-4	516.20	515.93	45										6	0.60%
7-7	7-6	517.30	516.30	62										7	1.61%
OATS 8-5	8-4	532.92	532.39	90											0.59%
8-4	8-3	532.39	532.26	25										4	0.52%
8-3	8-2	532.26	532.14	25										3	0.48%
8-2	8-1	532.14	531.96	35										3	0.51%
OATS 9-6	9-2	532.44	531.94					160						2	0.31%
9-5	9-4	532.24	532.12	25										2	0.48%
9-4	9-3	532.12	531.99	25										4	0.52%
9-3	9-2	531.99	531.94	10										4	0.50%
9-2	9-1	531.94	531.83					16						37	0.69%
SUBTOTALS				837	65	426	123	435	0	310	0	0	0	476	
SUBTOTAL FROM ADJACENT TABLE				1,078	569	626	0	0	240	98	288	23	33	1,807	
TOTAL				1,915	634	1,052	123	435	240	408	288	23	33	2,283	

PIPE CULVERT SCHEDULE													
FROM	TO	UPSTREAM INVERT	DOWNSTREAM INVERT	P CUL CL A 2 30	P CUL CL C 1 6	P CUL CL D 1 18	PRC FLAR END SEC 18	PRC FLAR END SEC 30	TRENCH BACKFILL	SLOPE			
STATION OFFSET	STATION OFFSET	(FOOT)									(EACH)	(EACH)	(C.Y.)
SHILOH CUT-OFF													
18+85.20	25.26 RT	18+90.01	15.02 RT	612.34	610.39		12		3	15.67%			
49+82.48	37.86 LT	50+08.29	39.03 LT	532.10	531.97		26	2	8	0.50%			
49+82.48	37.86 LT	50+08.29	39.03 LT	532.10	531.97		26	2	8	0.50%			
51+26.10	43.37 RT	51+26.56	43.59 LT	530.84	530.59	87			2	0.29%			
TOTAL				87	12	52	4	2	100				

