

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION		CHANNEL EXCAVATION		ESTIMATED UNSUITABLE MATERIAL		SUITABLE MATERIAL ADJUSTED FOR SHRINKAGE		EMBANKMENT		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA 0+00 TO 4+61.8	52.9	0.0	0.0	0.0	0.0	39.7	1026.1	-986.4				
STA 4+61.8 TO 5+38.2	0.0	144.4	72.2	0.0	54.2	0.0	889.1	-869.7				
STA 5+38.2 TO 10+00	25.8	0.0	0.0	0.0	19.4	889.1	286.8	-286.8				
3 FIELD ENTRANCES	0.0	0.0	0.0	0.0	0.0	0.0	2202.0	-2088.7				
TOTAL	78.7	144.4	72.2	113.3	2202.0	-2088.7						


T.R.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
296B	08-09114-00-BR	HAMILTON	12	3
FED. ROAD DIST. NO. 9	ILLINOIS	FED. AID PROJECT		
PROJECT#	BROS-0651047	CONTRACT#	99454	
JOB NO. C-99-511-09	SOUTHERN OUTLET			

LEC JOB # H09L007HM

405 W. STATE ST.
SUITE 1
PRINCETON, IN 47160
PHONE: (812)-386-7611
FAX: (812)-385-2812



PROFESSIONAL DESIGN FIRM
LAND SURVEY & PROFESSIONAL ENGINEERING CORPORATION
184-00887
(82-032+35)(35-002769)



AARON M. MEFFORD
NAME
SIGNATURE
DATE
11-30-11
EXPIRES

TOWNSHIP ROUTE 296B
OVER SOUTHERN OUTLET
HAMILTON COUNTY, ILLINOIS

SHEET TITLE:
CROSS-SECTIONS
SCALE: 1" = 5'
BY: AMM
DATE: 2/2/11
REV:
3 OF 12 SHEETS
SHEET NO. 3