



FABRIC BEARING PAD
(Interior - 14 Req'd)




FABRIC BEARING PAD
(Exterior - 4 Req'd)

FIXED


Notes:
All bearing pads shall be 1" thick.
Omit holes when using expansion bearings.
Expansion bearing pad shall be bonded to the substructure.




SECTION A-A




TYPICAL TRANSVERSE TIE ASSEMBLY




BAR S(E)




BAR S₂(E)




BAR S₁(E)



BAR UE(E)




BAR U₁(E)



PLAN VIEW

NOTES

Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter shall be 1/2" and the nominal cross-sectional area shall be 0.153 sq. in. The 1" diameter rods in the transverse tie assembly shall be tightened to a snug fit and the threads set. Pockets on exterior faces of bridge shall be filled with grout after transverse tie assembly is in place.
Reinforcement bars shall conform to ASTM A 706, Grade 60. (See Special Provisions).
Two 1/8" fabric adjusting shims of the dimensions of the exterior bearing pad shall be provided for each bearing pad location.
A minimum 2 1/2" diameter lifting pin shall be used to engage the lifting loops during handling.
Corrosion Inhibitor, per Article 1020.05(b)(12) and 1021.06 of the Standard Specifications, shall be used in the concrete for precast prestressed concrete deck beams.
Compressive strength of prestressed concrete, f'c, shall be 6000 psi.
Compressive strength of prestressed concrete at release, f'ci, shall be 5000 psi.
All reinforcement shall be epoxy coated.



LIFTING LOOP DETAIL

BILL OF MATERIAL

Precast Prestressed Conc. Deck Bms. (33" depth)	Sq. Ft.	1,800
---	---------	-------

PD-3336-OD 7-1-10

FILE NAME = 090262-ah-bridge.dgn	USER NAME =	DESIGNED - A.S.L.	REVISED -
HAMPTON, LENZINI AND RENWICK, INC.		CHECKED - S.W.M.	REVISED -
268 STEVENSON DRIVE, SUITE 201		DRAWN - D.A.B.	REVISED -
SPRINGFIELD, ILLINOIS 62703		CHECKED - S.W.M.	REVISED -
ILLINOIS PROFESSIONAL DESIGN FIRM	PLOT SCALE =		
LS / PE / SE CORP. 194.00058	PLOT DATE = 2/15/2011		

STATE OF ILLINOIS
HAMILTON COUNTY HIGHWAY DEPARTMENT

33" x 36" PPC DECK BEAM DETAILS
STRUCTURE NO. 033-3314

SHEET NO. 3 OF 8 SHEETS

T.R.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
296B	08-09114-00-BR	HAMILTON	12	7
SOUTH CROUCH ROAD DISTRICT			CONTRACT NO. 99454	
[ILLINOIS] FED. AID PROJECT BROS-0105(049)				