



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2, 2022

SUBJECT FAP Route 346; FAU Route 1223 (US 41; Washington St.)
Project NHPP-STP-66GC(527)
Section 2021-077-B-R&FL
Lake County
Contract No. 62P14
Item No. 5, June 17, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions.
2. Added page 169 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

STRUCTURAL STEEL REMOVAL	46
REMOVE FIBER OPTIC CABLE FROM CONDUIT	47
TEMPORARY TRAFFIC SIGNAL INSTALLATION	47
TEMPORARY TRAFFIC SIGNAL TIMING	54
TEMPORARY VIDEO DETECTION	55
TEMPORARY PAVEMENT.....	56
CONTRACTOR'S RIGHT OF ENTRY AGREEMENT	57
UP'S RIGHT OF ENTRY INSTRUCTIONS TO THE CONTRACTOR.....	79
RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE)	90
DECK SLAB REPAIR.....	91
BRIDGE DECK LATEX CONCRETE OVERLAY.....	97
STRUCTURAL REPAIR OF CONCRETE	108
STRUCTURAL STEEL REPAIR	118
DIAMOND GRINDING AND SURFACE TESTING BRIDGE SECTIONS	119
SLIPFORM PARAPET	124
BRIDGE DECK CONSTRUCTION	129
BRIDGE DECK GROOVING (LONGITUDINAL)	130
PREFORMED PAVEMENT JOINT SEAL.....	131
AGGREGATE SUBGRADE IMPROVEMENT (BDE)	138
BLENDED FINELY DIVIDED MINERALS (BDE).....	140
COMPENSABLE DELAY COSTS (BDE).....	141
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	144
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	146
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE).....	156
STEEL COST ADJUSTMENT (BDE).....	157
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	160
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	160
TRAINING SPECIAL PROVISIONS (BDE)	161
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	164
WEEKLY DBE TRUCKING REPORTS (BDE).....	166
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	166
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	169

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Site 3630V-4: Bridge, 3600 Washington Street, Gurnee, Lake County

- Station 57+25 to Station 58+55 (CL US 41), 0 to 90 feet LT: The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). COC sampling parameter: Manganese.
- Station 57+25 to Station 58+60 (CL US 41), 0 to 75 feet RT: The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). COC sampling parameter: Manganese.
- Station 59+60 to Station 61+60 (CL US 41), 0 to 75 feet LT: The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). COC sampling parameter: Benzo(a)pyrene.
- Station 59+80 to Station 61+60 (CL US 41), 0 to 70 feet RT: The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). COC sampling parameter: Manganese.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

None

Added 6/2/2022