



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 6, 2022

SUBJECT: Route FAS 797 (CH 1)
Section 19-00127-00-SP
Wayne County
Contract No. 95924
Item 131
June 17, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 7 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

PAVEMENT REMOVAL

This work shall be done in accordance to Section 440 of the Standard Specifications except as described herein.

All excess clean fill material to be stock-piled for county use at a location approved by the County Engineer. Haul distance not to exceed 15 miles from work zone.

Basis of Payment. This work will not be paid for separately, but shall be included in the contract unit price CU YD for PAVEMENT REMOVAL.

UNDERGROUND CONDUIT

This work shall consist of furnishing and installing a conduit of the type and size specified, in accordance with Section 810 of the Standard Specifications except as described herein.

When PVC is specified, the substitution of Coilable Nonmetallic Conduit, in accordance with Article 1088.01 (c), in place of the PVC conduit of the size and type specified in the plans is permitted with no change in compensation for this item.

A 1/4" polypropylene pull rope shall be installed in all conduit runs exceeding 20 feet. A minimum of 2 feet of rope shall be provided at each end of a conduit run.

This work will be paid for at the contract unit price per FOOT for UNDERGROUND CONDUIT, of the size and type specified.

GULFBOX JUNCTION

This work shall consist of furnishing and installing a gulfbox junction in accordance with Section 815 and Articles 1088.07 of the Standard Specifications except as described herein.

The box and cover shall be made of composite concrete. The box shall be bottomless and 10" wide, 15" long, and 18" deep. All covers shall be rated a minimum of tier 22.

This work will be paid for at the contract unit price EACH for GULFBOX JUNCTION.