


\* MEET EXISTING CROSS SLOPES AND ELEVATIONS. FIELD VERIFY AND ADJUST AS NECESSARY.

PAVEMENT CROSS SLOPE AND ELEVATION - TEMP RAMP NW

STATION TEMP RAMP NW	LT EOP			PGL (= RT EOP)		
	O/S	%	ELEV.	O/S	%	ELEV.
1510+23.90	-11.00	1.50%	578.54	0.00	N/A	578.37
1510+30.00	-11.00	1.89%	578.47	0.00	N/A	578.26
1510+40.00	-11.00	2.52%	578.36	0.00	N/A	578.08
1510+50.00	-11.00	3.16%	578.25	0.00	N/A	577.90
1510+60.00	-11.13	3.79%	578.14	0.00	N/A	577.72
1510+70.00	-11.58	4.43%	578.05	0.00	N/A	577.54
1510+75.90	-12.00	4.80%	578.01	0.00	N/A	577.43

1511+66.08	-11.00	4.80%	577.10	0.00	N/A	576.57
1511+70.00	-11.00	4.55%	577.09	0.00	N/A	576.59
1511+80.00	-11.00	3.92%	577.10	0.00	N/A	576.67
1511+90.00	-11.00	3.28%	577.13	0.00	N/A	576.77
1512+00.00	-11.00	2.65%	577.15	0.00	N/A	576.86
1512+10.00	-11.00	2.01%	577.18	0.00	N/A	576.96
1512+20.00	-11.00	1.38%	577.21	0.00	N/A	577.06
1512+30.00	-11.00	0.74%	577.24	0.00	N/A	577.16
1512+40.00	-11.00	0.11%	577.26	0.00	N/A	577.25
1512+50.00	-11.00	-0.53%	577.29	0.00	N/A	577.35
1512+58.08	-11.00	-1.04%	577.32	0.00	N/A	577.43



- NOTES:
1. UNLESS OTHERWISE NOTED THE PGL IS ASSUMED TO BE AT THE BASELINE
  2. NC=2.00%

PAVEMENT CROSS SLOPE TRANSITIONS

**TEMPORARY RAMP NW  
STAGE 1  
SUPERELEVATION TRANSITION**

FILE PATH = C:\Users\pmsarno\Desktop\Drawings\26-14\0160W28-sht-SuperTrans Det-03.dgn



D160W28-sht-SuperTrans Det-03.dgn  
 USER NAME = pmsarno  
 PLOT SCALE = 40.0000' / in.  
 PLOT DATE = 4/26/2014

DESIGNED - KAM  
 DRAWN - NSA  
 CHECKED - KCF  
 DATE - 04/28/14

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUPERELEVATION TRANSITION DETAILS  
TEMPORARY RAMP NW (STAGE 1)**

SCALE: 1"=20'    SHEET 3 OF 4 SHEETS    STA.    TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	77
CONTRACT NO. 60W28				
ILLINOIS FED. AID PROJECT				