

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000-2A 80% FED. 20% STATE						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	255	255															
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	25	25															
40600300	AGGREGATE (PRIME COAT)	TON	127	127															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	47	47															
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	1301	1301															
40600895	CONSTRUCTING TEST STRIP	EACH	1	1															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	173	173															
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2650	2650															
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	31542	31542															
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	448	448															
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	60	60															
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	1056	1056															
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1018	1018															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1															
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3629	3629															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	122.0	122.0															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30127	30127															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	42.0	42.0															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	403	403															
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	122.0	122.0															
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30127	30127															
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	42.0	42.0															
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	185	185															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	148	148															
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4															
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0															

* SPECIALTY ITEMS

FILE NAME =	USER NAME = abreuth	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COAL CITY RD. FROM ILL 113 / DIVISION ST. TO ILL 53 SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\DOT\ABREUTH\0195053\01952210-Desig.dwg	DRAWN -	REVISED -	0383			113 X-RS-3	WILL	15	3	
PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60K53							
PLOT DATE = 4/30/2010	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT