

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM	ITEM DESCRIPTION	UNIT	CMAQ 80% LOCAL 20%		CONSTRUCTION TYPE CODE	
				TOTAL QUANTITY		SFTY-1B	Y002-1C
	20200100	EARTH EXCAVATION	CU YD	132		132	
	20800150	TRENCH BACKFILL	CU YD	46		46	
	21101615	TOPSOIL-FURNISH AND PLACE, 4"	SQ YD	224		224	
	25100630	EROSION CONTROL BLANKET	SQ YD	224		224	
	25200110	SODDING, SALT TOLERANT	SQ YD	224		224	
	25200200	SUPPLEMENTAL WATERING	UNIT	10		10	
	28000510	INLET FILTERS	EACH	7		7	
	35102000	AGGREGATE BASE COURSE, TYPE B, 8"	SQ YD	299		299	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	149		149	
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	56		56	
	42001300	PROTECTIVE COAT	SQ YD	114		114	
	42400430	PORTLAND CEMENT SIDEWALK, 5"	SQ FT	565		565	
	42400800	DETECTABLE WARNINGS	SQ FT	80		80	
	44000100	PAVEMENT REMOVAL	SQ YD	179		179	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	48		48	
	44000600	SIDEWALK REMOVAL	SQ FT	100		100	
	550A0340	STORM SEWERS, CLASS A, TYPE 2 - 12"	FOOT	55		55	
	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1		1	
	60600605	CONCRETE CURB, TYPE B	FOOT	92		92	
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	24		24	
	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	24		24	
	60618800	CONCRETE MEDIAN, TYPE SB	SQ FT	80		80	
	67100100	MOBILIZATION	L SUM	1		1	
	70102620	TRAFFIC CONTROL AND PROTECTION - STANDARD 701501	L SUM	1		1	
	70102625	TRAFFIC CONTROL AND PROTECTION - STANDARD 701606	L SUM	1		1	
	70102630	TRAFFIC CONTROL AND PROTECTION - STANDARD 701601	L SUM	1		1	
	70102635	TRAFFIC CONTROL AND PROTECTION - STANDARD 701701	L SUM	1		1	
	70102640	TRAFFIC CONTROL AND PROTECTION - STANDARD 701801	L SUM	1		1	
*	72000100	SIGN PANEL - TYPE 1	SQ FT	642			642
*	72400500	RELOCATE SIGN PANEL ASSEMBLY, TYPE A	EACH	105			105
*	72900210	METAL POST, TYPE B	EACH	206			206
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3,479		3479	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,000		10000	
*	78003100	PREFORMED PLASTIC PAVEMENT MARKING - TYPE B LETTERS & SYMBOLS	SQ FT	226		226	
*	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	96		96	
*	78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	224		224	
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	100		100	