

80% SIDEWALK (L/EP)
20% LOCAL

80% SIDEWALK (L/AD)
20% LOCAL

DEERFIELD PEDESTRIAN
80% WALKWAY (L/AD)
20% LOCAL

80% LIGHTING (L/AD)
20% LOCAL

TRAFFIC SIGNALS
80% FED (L/EP)
20% LOCAL

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				SFTY-1B	SFTY-1B	X928-2A	Y030-1E	Y031-1F
60109580	PIPE UNDERDRAIN FOR STRUCTURES 4"	FOOT	206.5		40	166.5		
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	3	3				
63400205	GUARD POSTS REMOVAL	EACH	1	1				
67100100	MOBILIZATION	L SUM	1		1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1	
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1				1	
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	383				133	250
* 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	91				91	
* 81100220	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA., PVC COATED GALVANIZED STEEL	FOOT	8				8	
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	39				39	
* 81200100	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	62				62	
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	4				4	
* 81303950	JUNCTION BOX EMBEDDED IN STRUCTURE, 6" X 6" X 6"	EACH	5				5	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	1					1
* 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	200				200	
* 81702410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 4	FOOT	158				158	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	221				221	
* 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1				1	
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1				1	
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1				1	
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1				1	
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1					1
550A0030	STORM SEWERS, CLASS A, TYPE 1 8"	FOOT	24	24				
X0321865	ANTI-GRAFFITI PROTECTION SYSTEM	SQ FT	2,581			2,581		
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	690					690
X0323992	HELICAL GROUND ANCHORS	EACH	9			9		
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	1,778			1,778		
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1				
* X8161000	EXPOSE AND RELOCATE EXISTING UNIT DUCT	FOOT	16				16	
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	690					690
XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	410	410				
XX001607	RETAINING WALL, SPECIAL	SQ FT	135			135		
XX003308	TRENCH DRAINS	FOOT	180			180		

• SPECIALTY ITEMS

McDonough Associates Inc.
 Engineers / Architects
 130 East Randolph Street, Chicago, Illinois 60601

FILE NAME = D:\sht-S0002.dgn
 USER NAME = Jmddiet
 PLOT SCALE = 1:120
 PLOT DATE = 4/13/2010

DESIGNED - JWM	REVISED -
DRAWN - JWM	REVISED -
CHECKED - RY	REVISED -
DATE - 04/09/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1257	08-00083-00-BT	LAKE	51	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63450	