



* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

1. MILL HMA FIRST IF THERE IS AT LEAST 4 1/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| | | | | | | | | | | | | |
|--|---------------------|----------------------------|-----------------------------|---|--|------------------|--------|------------------------|---------------------------|-------------------------------------|-----------------------|--------------------|
| FILE NAME = c:\projects\diststd22x34\bd22.dgn | USER NAME = bauerdl | DESIGNED - R. SHAH | REVISED - A. ABBAS 04-27-98 | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT | | | F.A.U. RTE. 1342 | SECTION 10-00036-00-RS | COUNTY KANE | TOTAL SHEETS 21 | SHEET NO. 13 |
| PLOT SCALE = 50.000' / IN. | CHECKED - | REVISOR - R. BORO 01-01-07 | REVISOR - R. BORO 09-04-07 | | SCALE: NONE | SHEET NO. 1 OF 1 | SHEETS | STA. | TO STA. | BD400-04 (BD-22) CONTRACT NO. 63469 | | |
| PLOT DATE = 10/27/2008 | DATE - 10-25-94 | REVISOR - K. ENG 10-27-08 | | | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003 (608) | | | | | | | |
| | | | | | C-61-437-10 | | | | | | | |