

**SUMMARY OF QUANTITIES  
CONSTRUCTION TYPE CODE I000**

CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1566
40600300	AGGREGATE (PRIME COAT)	TON	2
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	348
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	206
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N50	TON	1755
S 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1334
42400800	DETECTABLE WARNINGS	SQ FT	176
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	15662
44000500	COMBINATION CURB AND GUTTER REMOVAL	FDDT	1010
44201701	CLASS D PATCHES, TYPE I 5 INCH	SQ YD	50
44201705	CLASS D PATCHES, TYPE II 5 INCH	SQ YD	50
44201709	CLASS D PATCHES, TYPE III 5 INCH	SQ YD	75
44201711	CLASS D PATCHES, TYPE IV 5 INCH	SQ YD	75
44000600	SIDEWALK REMOVAL	SQ FT	1303
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	13
S 60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	3
S 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FDDT	1010
67100100	MOBILIZATION	L SUM	1
S 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
S 70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
S 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
S 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FDDT	1200
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	186
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4'	FDDT	7010
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6'	FDDT	6684
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12'	FDDT	876
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24'	FDDT	203
S * X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	3
44201670	CLASS D PATCHES, TYPE I 2 INCH	SQ YD	50
44201672	CLASS D PATCHES, TYPE II 2 INCH	SQ YD	50
44201674	CLASS D PATCHES, TYPE III 2 INCH	SQ YD	75
44201676	CLASS D PATCHES, TYPE IV 2 INCH	SQ YD	75
S X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1

\* = DENOTES SPECIALTY ITEM  
S = SPECIAL PROVISION

FILE NAME =	USER NAME =	DESIGNED -- KRY	REVISED -- 4/7/2010 PER IDOT	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WESTERN AVENUE LAPP QUANTITY SHEET	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -- KRY	REVISED -- 4/17/2010 PER IDOT			2411	10-00076-00-RS	KANE	16	3	
		CHECKED -- NAB	REVISED -- 5/26/10 PER IDOT			SCALE: NTS		SHEET NO. 3 OF 16 SHEETS		STA. TO STA.	
		PLOT SCALE =	DATE -- 4/7/2010					ILLINOIS FED. AID PROJECT		CONTRACT NO. 63476	
		PLOT DATE = 5/27/2010	REVISED --								