

**SUMMARY OF QUANTITIES**  
ANDERSON BOULEVARD IMPROVEMENTS

PAY ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	LAPP ROADWAY	NON PARTICIPATING
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	29.00	29.00	
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	29.00	29.00	
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	29.00	29.00	
21101615	TOPSOIL, FURNISH AND PLACE, 4"	SQ YD	1556.00	1556.00	
25000100	SEEDING, CLASS 1	ACRE	0.32	0.32	
25100125	MULCH METHOD 3	ACRE	0.32	0.32	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1671.00	1671.00	
40600300	AGGREGATE (PRIME COAT)	TON	26.00	26.00	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	902.00	902.00	
40600895	CONSTRUCTING TEST STRIP	EACH	1.00	1.00	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	781.00	781.00	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50, (IL-9.5mm)	TON	2168.00	2168.00	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	49.00		49.00
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6022.00	6022.00	
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	849.00	849.00	
42400605	SIDEWALK REPAIR (SPECIAL)	SQ FT	113.00		113.00
42400800	DETECTABLE WARNINGS	SQ FT	360.00	360.00	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	16399.00	16399.00	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	76.00		76.00
44000600	SIDEWALK REMOVAL	SQ FT	6828.00	6828.00	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	265.00	265.00	
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	50.00	50.00	
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2.00		2.00
60219300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	5.00		5.00
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	11.00		11.00
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	19.00	19.00	
67100100	MOBILIZATION	L SUM	1.00	1.00	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3.00	3.00	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.00	1.00	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.00	1.00	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	59.00	59.00	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	310.00	310.00	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500.00	500.00	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	144.00	144.00	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	91.00	91.00	
88600600	DETECTOR LOOP REPLACEMENT	FOOT	250.00	250.00	
X0324942	GROUT REMOVAL AND REPLACEMENT	EACH	5.00		5.00
Z0004514	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 4"	SQ YD	27.00		27.00

CITY OF GENEVA KANE COUNTY, ILLINOIS	DESIGNED - CED	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION ANDERSON BLVD LAPP IMPROVEMENTS	SUMMARY OF QUANTITIES		F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - HL PM	REVISED -		1678	10-00111-00-RS	KANE	22	5		
	CHECKED - PB	REVISED -		JOB NO. C-91-545-10	FED. ROAD DIST. NO. C-91-545-10	CONTRACT NO. 63478				
	DATE - APRIL 2010	REVISED -		SCALE: _____	STA. 0+00 TO STA. 34+22	ILLNOIS	FED. AID PROJECT ARA-9003(679)			