

SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE 1000	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	48
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1
25200110	SODDING, SALT TOLERANT	SQ YD	48
25200200	SUPPLEMENTAL WATERING	UNIT	5
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	156
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,270
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD) IL-4.75, N50	TON	516
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	115
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,077
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,400
42400800	DETECTABLE WARNINGS	SQ FT	84
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	12,701
44000195	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ YD	57
44000600	SIDEWALK REMOVAL	SQ FT	1,400
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	65
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	22
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	9
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE-1 FRAME, AND OPEN LID	EACH	3
60266600	VALVE BOXES TO BE ADJUSTED	EACH	12

SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE 1000	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	940
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6,900
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	3,334
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	411
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	92
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE-1 FRAME, CLOSED LID	EACH	19
Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	57

\* SPECIALTY ITEM



VILLAGE OF HOMEWOOD  
ENGINEERING  
DIVISION

USER NAME	DESIGNED	REVISION
	DJA	--
	DJA	--
PLOT SCALE	CHECKED	REVISION
--	MM	--
PLOT DATE	DATE	REVISION
--	04-28-10	--

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 12 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2845	10-00130-00-RS	COOK	12	2
CONTRACT NO. 63479				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				