

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM DESCRIPTION	UNITS	CONSTRUCTION TYPE CODE 1000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,944
40600300	AGGREGATE (PRIME COAT)	TON	10
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,693
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	360
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,385
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY, 8"	SQ YD	100
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,500
42400800	DETECTABLE WARNINGS	SQ FT	168
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	40,293
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	150
44000600	SIDEWALK REMOVAL	SQ FT	3,500
44001700	COMB CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,200
48101200	AGGREGATE SHOULDERS, TYPE B	TON	80
60252710	CATCH BASINS TO BE ADJUSTED WITH SPECIAL FRAME AND GRATE	EACH	10
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	22
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
70106810	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL MO	2
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6,500
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	464
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28,776
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,850
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,300
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	900
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,262
X4420132	CLASS D PATCHES (SPECIAL)	SQ YD	110
XX006425	RESTORATION	SQ YD	533
Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	50
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

* SPECIALTY ITEM



CITY OF AURORA
ENGINEERING DIVISION
44 EAST DOWNER PLACE

DESIGNED - CHRIS LIROT	REVISED - 4/15/10
DRAWN - ALBERTO SANCHEZ	REVISED -
CHECKED - CHRIS LIROT	REVISED -
DATE - 10/1/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE

SHEET NO. 1 OF 1 SHEETS

STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET
1503	10-00290-00-RS	KANE	14 3
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	
		CONTRACT NO. 63483	