

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY J000 80% FED 20% STATE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	18317.1	18317.1
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	8563.7	8563.7
20101000	TEMPORARY FENCE	FOOT	3174	3174
20101100	TREE TRUNK PROTECTION	EACH	400	400
20200100	EARTH EXCAVATION	CU YD	101700	101700
20200200	ROCK EXCAVATION	CU YD	27153	27153
<b>50200450</b>	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	120	120
20400800	FURNISHED EXCAVATION	CU YD	56036	56036
20800150	TRENCH BACKFILL	CU YD	734	734
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	22735	22735
* 25000100	SEEDING, CLASS 1	ACRE	1.5	1.5
* 25000210	SEEDING, CLASS 2A	ACRE	28.75	28.75
* 25000310	SEEDING, CLASS 4	ACRE	5.5	5.5
* 25000312	SEEDING, CLASS 4A	ACRE	14.25	14.25
* 25000322	SEEDING, CLASS 5A	ACRE	5.5	5.5
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4380	4380
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4380	4380
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4380	4380
:) 25000750	MOWING	ACRE	28.75	28.75
25000775	SELECTIVE MOWING STAKES	EACH	8	8
* 25001845	SEEDING, CLASS 7 (SPECIAL)	ACRE	17	17
* 25100115	MULCH, METHOD 2	ACRE	23.75	23.75
* 25100630	EROSION CONTROL BLANKET	SQ YD	197901	197901
* 25100900	TURF REINFORCEMENT MAT	SQ YD	1234	1234
* 25101010	HYDRAULIC MULCH	POUND	7192	7192
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	56200	56200
28000305	TEMPORARY DITCH CHECKS	FOOT	3970	3970
28000400	PERIMETER EROSION BARRIER	FOOT	48269	48269
28000500	INLET AND PIPE PROTECTION	EACH	54	54
28100105	STONE RIPRAP, CLASS A3	SQ YD	3196	3196
28100107	STONE RIPRAP, CLASS A4	SQ YD	672	672
28100111	STONE RIPRAP, CLASS A6	SQ YD	164	164
28100201	STONE RIPRAP, CLASS A1	TON	6623	6623
28100210	STONE RIPRAP, CLASS A5 (SPECIAL)	TON	4548	4548
28200200	FILTER FABRIC	SQ YD	899	899
* 28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	19743	19743

\* SPECIALTY ITEM  
:) NON-PARTICIPATING (100% STATE)

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pw_work\PWIDOT\CUSHMANBW\dms31213\d06608cwr.dgn		DRAWN -	REVISED -			742	37R-4	OGLE	867	3	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64E17					
PLOT DATE = Wed Apr 07 14:29:34 2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					