

SUMMARY OF QUANTITIES

| CODE NUMBER | ITEM | UNIT | TOTAL QUANTITY | ROADWAY J000 80% FED 20% STATE |
|-------------|--|-------|----------------|---|
| 31100910 | SUB-BASE GRANULAR MATERIAL, TYPE A 12" | SQ YD | 152127 | 152127 |
| 31100935 | SUB-BASE GRANULAR MATERIAL, TYPE A 18" | SQ YD | 3424 | 3424 |
| 31100965 | SUB-BASE GRANULAR MATERIAL, TYPE A 24" | SQ YD | 53110 | 53110 |
| 35101400 | AGGREGATE BASE COURSE, TYPE B | TON | 17917 | 17917 |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 44.9 | 44.9 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 12.9 | 12.9 |
| 40600525 | LEVELING BINDER (HAND METHOD), N50 | TON | 5 | 5 |
| 40600625 | LEVELING BINDER (MACHINE METHOD), N50 | TON | 148 | 148 |
| 40600990 | TEMPORARY RAMP | SQ YD | 69.4 | 69.4 |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 222 | 222 |
| 40702700 | FURNISH PROFILOGRAPH | L SUM | 1 | 1 |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 1978 | 1978 |
| 42000411 | PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED) | SQ YD | 137630 | 137630 |
| 42001300 | PROTECTIVE COAT | SQ YD | 41531 | 41531 |
| 42001500 | P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT | SQ YD | 109 | 109 |
| 42300300 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH | SQ YD | 162 | 162 |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 92693 | 92693 |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 2645 | 2645 |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 139 | 139 |
| 44000400 | GUTTER REMOVAL | FOOT | 1890 | 1890 |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 343 | 343 |
| 44002400 | CURB REMOVAL (SPECIAL) | FOOT | 4 | 4 |
| 44002805 | ISLAND REMOVAL | SQ FT | 844 | 844 |
| 44004000 | PAVED DITCH REMOVAL | FOOT | 619 | 619 |
| 44004300 | PAVEMENT BREAKING | SQ YD | 20308 | 20308 |
| 44200126 | PAVEMENT PATCHING, TYPE IV, 10 INCH | SQ YD | 2204 | 2204 |
| 44212900 | PAVEMENT PATCHING (PARTIAL DEPTH) | SQ YD | 2204 | 2204 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 139 | 139 |
| 48300410 | PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2" | SQ YD | 70023 | 70023 |
| 50100300 | REMOVAL OF EXISTING STRUCTURES NO. 1 | EACH | 11 | 11 |
| 50100400 | REMOVAL OF EXISTING STRUCTURES NO. 2 | EACH | 2 | 2 |
| 50100500 | REMOVAL OF EXISTING STRUCTURES NO. 3 | EACH | 4 | 4 |
| 50100600 | REMOVAL OF EXISTING STRUCTURES NO. 4 | EACH | 4 | 4 |
| 50100700 | REMOVAL OF EXISTING STRUCTURES NO. 5 | EACH | 5 | 5 |
| 50100800 | REMOVAL OF EXISTING STRUCTURES NO. 6 | EACH | 1 | 1 |
| 50100900 | REMOVAL OF EXISTING STRUCTURES NO. 7 | EACH | 1 | 1 |
| 50101000 | REMOVAL OF EXISTING STRUCTURES NO. 8 | EACH | 2 | 2 |
| 50101100 | REMOVAL OF EXISTING STRUCTURES NO. 9 | EACH | 1 | 1 |

* SPECIALTY ITEM

| | | | | | | | | | | |
|--|-----------------------|------------|-----------|---|----------------------------------|----------------|---------|--------|--------------|---------------------------|
| FILE NAME = | USER NAME = cushmanbw | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| ct:\pw\work\PIWIDOT\CUSHMANBW\dms31213\d06808cvr.dgn | | DRAWN - | REVISED - | | | 742 | 37R-4 | OGLE | 867 | 4 |
| PLOT SCALE = 50.0000' / IN. | | CHECKED - | REVISED - | | SCALE: | | | | | |
| PLOT DATE = Wed Apr 07 14:29:47 2010 | | DATE - | REVISED - | | SHEET NO. OF SHEETS STA. TO STA. | | | | | CONTRACT NO. 64E17 |
| | | | | | | | | | | ILLINOIS FED. AID PROJECT |