

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY J000 80% FED 20% STATE
60603400	GUTTER OUTLET (SPECIAL)	EACH	1	1
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	645	645
60900330	TYPE D INLET BOX, STANDARD 609001	EACH	4	4
60900515	CONCRETE THRUST BLOCKS	EACH	4	4
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	10950	10950
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	50	50
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	18.75	18.75
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	14	14
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	15	15
63200310	GUARDRAIL REMOVAL	FOOT	9811	9811
63500105	DELINEATORS	EACH	193	193
64200105	SHOULDER RUMBLE STRIPS	FOOT	67003	67003
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	9051	9051
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	266	266
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	52	52
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	30	30
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	270	270
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	3	3
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	36	36
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	750	750
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	95987	95987
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	78	78
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1887	1887
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1287.5	1287.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1287.5	1287.5
* 72000100	SIGN PANEL - TYPE 1	SQ FT	19	19
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	945	945
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	90	90
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	17	17

* SPECIALTY ITEM

FILE NAME = c:\pwwork\PIWIDOT\CUSHMANBW\dms31213\d0660800vr.dgn	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 742	SECTION 37R-4	COUNTY OGLE	TOTAL SHEETS 867	SHEET NO. 7
PLOT SCALE = 50.0000' / IN.		DRAWN -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 64E17				
PLOT DATE = Wed Apr 07 14:38:28 2010		DATE -	REVISED -	ILLINOIS FED. AID PROJECT						