

# SCHEDULE OF QUANTITIES

44000100	PAVEMENT REMOVAL					REMARK'S
	SQ_YD	LOCATION				
	13555.7	LT/RT 680 + 0	TO	720 + 40		Includes existing bituminous shoulder's
	10351.5	LT/RT 722 + 22	TO	763 + 50		Includes existing bituminous shoulder's
	1316.9	LT/RT 764 + 50	TO	769 + 20		Includes existing bituminous shoulder's
	3255.0	LT/RT 770 + 76	TO	782 + 50		Includes existing bituminous shoulder's
	1539.4	LT/RT 787 + 50	TO	793 + 50		Includes existing bituminous shoulder's
	1847.9	LT/RT 797 + 50	TO	804 + 0		Includes existing bituminous shoulder's
	19029.1	LT/RT 823 + 0	TO	893 + 0		Includes existing bituminous shoulder's
	4858.8	LT/RT 896 + 0	TO	912 + 62		Includes existing bituminous shoulder's
	6897.0	LT/RT 915 + 81	TO	941 + 50		Includes existing bituminous shoulder's
	2349.7	LT/RT 949 + 50	TO	958 + 0		Includes existing bituminous shoulder's
	1423.8	LT/RT 967 + 50	TO	972 + 0		Includes existing bituminous shoulder's
	3032.7	LT/RT 975 + 0	TO	986 + 0		Includes existing bituminous shoulder's
	8439.9	LT/RT 1006 + 0	TO	1035 + 50		Includes existing bituminous shoulder's
	14795.4	LT/RT 1037 + 50	TO	1067 + 92		Includes existing bituminous shoulder's
	<u>92692.7</u>	TOTAL				

44000400	GUTTER REMOVAL					REMARK'S
	EQOI	LOCATION				
	200	LT. STA. 712 + 36	TO	714 + 36		
	455	RT. STA. 722 + 36	TO	726 + 91		w/ Inlet & Pipe Drain (15" CMP)
	523	LT. STA. 775 + 18	TO	780 + 35		w/ Outlet
	1042	RT. STA. 900 + 18	TO	910 + 60		Near Camling Rd.
	325	RT. STA. 5 + 0	TO	8 + 25		Mudd Creek Rd.
	<u>1890</u>	TOTAL				

44000600	SIDEWALK REMOVAL					REMARK'S
	SQ. FT.	LOCATION				
	202	RT. STA. 80 + 43	TO	81 + 3		Indian Cove Rd along Entrance
	141	LT. STA. 80 + 44	TO	80 + 82		Indian Cove Rd along Entrance
	<u>343</u>	TOTAL				

44002400	CURB REMOVAL (SPECIAL)					REMARK'S
	EQOI	LOCATION				
	2	RT. STA. 720 + 61	TO	720 + 63		Mudd Creek Bridge SE
	2	RT. STA. 722 + 30	TO	722 + 32		Mudd Creek Bridge NE
	<u>4</u>	TOTAL				

44002805	ISLAND REMOVAL					REMARK'S
	SQ. FT.	LOCATION				
	448.2	LT. STA. 724 + 5				MUD CREEK RD.
	54.5	LT. STA. 1060 + 28				IL 72 (SW) - Removed prior to Stage 1
	340.9	LT. STA. 1060 + 93				IL 72 (NW)
	<u>843.6</u>	TOTAL				

44004000	PAVED DITCH REMOVAL					REMARK'S
	EQOI	LOCATION				
	20	LT. STA. 750 + 33	TO	750 + 53		PE Entrance 750+71
	6.4	RT. STA. 753 + 76	TO	754 + 37		North of Indian Cove Rd.
	30	LT. STA. 774 + 56	TO	774 + 60		PE Entrance 774+97
	505	RT. STA. 922 + 41	TO	927 + 43		North of PE 922+05
	<u>619</u>	TOTAL				

44004300	PAVEMENT BREAKING					REMARK'S
	SQ_YD	LOCATION				
	265.4	LT/RT 763 + 50	TO	764 + 50		
	1288.9	LT/RT 782 + 50	TO	787 + 50		
	1035.3	LT/RT 793 + 50	TO	797 + 50		
	5381.9	LT/RT 804 + 0	TO	823 + 0		
	814.7	LT/RT 893 + 0	TO	896 + 0		
	2164.4	LT/RT 941 + 50	TO	949 + 50		
	2600.6	LT/RT 958 + 0	TO	967 + 50		
	800.2	LT/RT 972 + 0	TO	975 + 0		
	5417.6	LT/RT 986 + 0	TO	1006 + 0		
	538.9	LT/RT 1035 + 50	TO	1037 + 50		
	<u>20308.0</u>	TOTAL				

50100300	REMOVAL OF EXISTING STRUCTURES NO. 1					REMARK'S
	EACH	LOCATION				
	1	LT/RT 686 + 5				3x2 Concrete Box Culvert
	1	LT/RT 690 + 95				2.5x2 Concrete Box Culvert
	1	LT/RT 693 + 77				24" RCP
	1	LT/RT 696 + 55				2x2 Concrete Box Culvert
	1	LT/RT 701 + 8				24" RCP
	1	LT/RT 705 + 28				4x3 Concrete Box Culvert
	1	LT/RT 708 + 76				2.5x2 Concrete Box Culvert
	1	LT/RT 716 + 5				2x2 Concrete Box Culvert
	1	LT/RT 744 + 1				3x2 Concrete Box Culvert
	1	LT/RT 999 + 1				2x2 Concrete Box Culvert
	1	LT/RT 1003 + 60				2x1.5 Concrete Box Culvert
	<u>11</u>	TOTAL				

50100400	REMOVAL OF EXISTING STRUCTURES NO. 2					REMARK'S
	EACH	LOCATION				
	1	LT/RT 860 + 65				2x2 Concrete Box Culvert
	1	LT. STA. 1010 + 58				2.5x1.5 Concrete Box Culvert
	<u>2</u>	TOTAL				

50100500	REMOVAL OF EXISTING STRUCTURES NO. 3					REMARK'S
	EACH	LOCATION				
	1	LT/RT 754 + 54				3x2 Concrete Box Culvert (not to be replaced)
	1	LT/RT 812 + 49				3.5x3.5 Concrete Box Culvert
	1	LT/RT 899 + 50				2 - 24" RCP
	1	LT/RT 962 + 88				3x1.5 Concrete Box Culvert
	<u>4</u>	TOTAL				

50100600	REMOVAL OF EXISTING STRUCTURES NO. 4					REMARK'S
	EACH	LOCATION				
	1	LT/RT 747 + 50				5.5x3.5 Concrete Box Culvert
	1	LT/RT 1024 + 6				6x3.5 Concrete Box Culvert
	1	LT/RT 1042 + 24				8x2 Concrete Box Culvert
	1	LT/RT 1050 + 38				6x1.5 Concrete Box Culvert
	<u>4</u>	TOTAL				

50100700	REMOVAL OF EXISTING STRUCTURES NO. 5					REMARK'S
	EACH	LOCATION				
	1	LT/RT 785 + 82				3x3 Concrete Box Culvert
	1	LT/RT 792 + 26				2x2 Concrete Box Culvert
	1	LT/RT 809 + 93				2x1.5 Concrete Box Culvert
	1	LT/RT 816 + 48				3.5x3.5 Concrete Box Culvert
	1	LT/RT 951 + 12				24" RCP
	<u>5</u>	TOTAL				

50100800	REMOVAL OF EXISTING STRUCTURES NO. 6					REMARK'S
	EACH	LOCATION				
	1	LT/RT 974 + 19				Double 6x2.5 Concrete Box Culvert
	<u>1</u>	TOTAL				

50100900	REMOVAL OF EXISTING STRUCTURES NO. 7					REMARK'S
	EACH	LOCATION				
	1	LT. STA. 148 + 0				Townline Rd. 12x6.5 Concrete Box Culvert (not to be replaced)
	<u>1</u>	TOTAL				

50101000	REMOVAL OF EXISTING STRUCTURES NO. 8					REMARK'S
	EACH	LOCATION				
	1	LT/RT 740 + 85				3x2 Concrete Box Culvert
	1	LT/RT 942 + 38				2x2 Concrete Box Culvert
	<u>2</u>	TOTAL				

50101100	REMOVAL OF EXISTING STRUCTURES NO. 9					REMARK'S
	EACH	LOCATION				
	1	LT/RT 832 + 78				10x7.5 Concrete Box Culvert (From Structure Plans S.N. 071-1135)
	<u>1</u>	TOTAL				