

EARTHWORK SCHEDULE /SEEDING SCHEDULE

LOCATION	20200100	20200200	20400800	EARTH WORK			21101505	25000100	25000210	25000310	25000312	25000312	25000322	25001845	25000400	25000500	25000600	25000750	25100115	25100630	25101010
	EARTH EXC (CUT)	ROCK EXC	FURNISHED EXC	EARTH EXC ADJ SHRINK 25% EARTH	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)	TOPSOIL EXCAVATION & PLACEMENT	SEEDING CLASS 1	SEEDING CLASS 2A	SEEDING CLASS 4	(ARTICULATED BLOCK REVET) SEEDING CLASS 4A	SEEDING CLASS 4A	SEEDING CLASS 5A	SEEDING CLASS 7 (SPL)	NITROGEN FERTILIZER NUTRIENTS	PHOSPHOROUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS	MOWING	MULCH METHOD 2	EROSION CONTROL BLANKET	HYDRAULIC MULCH
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	ACRE	ACRE	ACRE	ACRE	ACRE	ACRE	ACRE	POUND	POUND	POUND	ACRE	ACRE	SQ YD	LBS
680+00 - 692+00	3071.4			2304	1663.6	640.0			0.258		0.368	0.314		56.41	56.41	56.41	0.26		2771	1474	
692+00 - 706+00	3700.3			2775	1400.7	1374.5			0.120		0.528	0.147		58.33	58.33	58.33	0.12		1294	2113	
706+00 - 720+00	3580.0	132		2685	1306.4	1510.6			0.322		0.221	0.190		48.82	48.82	48.82	0.32		2474	884	
720+00 - 734+00	3315.5	6		2487	734.1	1758.5			0.351			0.234		31.56	31.56	31.56	0.35		2831		
734+00 - 748+00	3367.8	1		2526	1337.8	1189.1			0.545			0.303		49.07	49.07	49.07	0.55		4105		
748+00 - 762+00	2689.5			2017	733.1	1284.0			0.881			0.311		79.33	79.33	79.33	0.88		5771		
762+00 - 776+00	1458.1			1094	997.5	96.1			1.075			0.121		96.76	96.76	96.76	1.08		5788		
776+00 - 790+00	1609.4			1207	4140.5	-2933.5			1.150			0.152		103.48	103.48	103.48	1.15		6300		
790+00 - 804+00	3834.9			2876	5550.5	-2674.3			1.425			0.632		128.28	128.28	128.28	1.43		9958		
804+00 - 818+00	5333.1			4000	13581.8	-9582.0		0.871	0.560			0.716		128.85	128.85	128.85	0.56	0.871	6176		
818+00 - 832+00	5950.0			4463	3282.4	1180.1		0.156	1.282			0.556		129.43	129.43	129.43	1.28	0.156	8893		
832+00 - 846+00	2262.3			1697	14789.4	-13092.7	2204.5		2.017			0.049		181.52	181.52	181.52	2.02		10001		
846+00 - 860+00	2009.1			1507	5432.6	-3925.8	5384.2		1.716			0.229		154.45	154.45	154.45	1.72		9415		
860+00 - 874+00	6204.6			4653	431.8	4221.7	154.6		0.431			0.417		38.80	38.80	38.80	0.43		4107		
874+00 - 888+00	2559.1			1919	2966.7	-1047.4		0.067	1.328					125.57	125.57	125.57	1.33	0.067	6429		
888+00 - 902+00	4636.2			3477	3101.9	375.3		0.318	1.005			0.557		119.14	119.14	119.14	1.01	0.318	7562		
902+00 - 916+ 50	7846.8			5885	110.2	5774.9			0.775			0.609		69.75	69.75	69.75	0.78		6699		
916+50 - 930+ 50	4104.2			3078	2193.8	884.3	1882.6		1.016			0.406		91.43	91.43	91.43	1.02		6882		
930+50 - 944+ 50	4047.8			3036	2161.7	874.2	1498.6		0.789			0.387		71.01	71.01	71.01	0.79		5691		
944+50 - 958+ 50	3538.0			2654	1561.4	1092.1			0.857			0.496		77.09	77.09	77.09	0.86		6549		
958+50 - 972+ 50	1583.7			1188	14409.3	-13221.5			1.730			0.275		155.71	155.71	155.71	1.73		9705		
972+50 - 986+ 50	8973.1			6730	9731.3	-3001.5			1.231			0.935		110.83	110.83	110.83	1.23		10484		
986+50 - 1000+ 50	2020.8	16321		1516	11149.4	6687.1			0.675		0.681	0.196		121.99	121.99	121.99	0.67		4214	2722	
1000+50 - 1014+ 50	2145.8	8864		1609	18436.9	-7963.7	1537.2	0.300	1.771	0.300		1.260	0.300	294.36	294.36	294.36	1.77	1.800	14666		
1014+50 - 1028+ 50	1690.2			1268	28625.9	-27358.3	9081	5.000	1.510	5.000		1.734	5.000	1515.83	1515.83	1515.83	1.51	20.333	15699		
1028+50 - 1042+ 50	973.6	1		730	4613.3	-3882.1	990.5		0.755			0.381		67.98	67.98	67.98	0.76		5499		
1042+50 - 1056+ 50	1289.0			967	1813.8	-847.1			0.751			0.198		67.58	67.58	67.58	0.75		4594		
1056+50 - 1068+00	2466.9			1850	1426.6	423.6			1.284			0.066		115.60	115.60	115.60	1.28		6536		
SIDEROADS																					
Mudd Creek Rd.																					
5+00 - 9+ 50	896.3			672	1.6	670.6			0.110					9.93	9.93	9.93	0.11		534		
Indian Cove Rd.																					
80+50 - 81+00	114.5			86	0.9	85.0			0.012			0.003		1.11	1.11	1.11	0.01		74		
Town Hall Rd.																					
88+50 - 89+ 50	427.5			321	0.0	320.6			0.011			0.052		0.95	0.95	0.95	0.01		304		
Camling Rd.																					
96+50 - 99+ 50	2524.3	1828		1893	0.0	3721.4			0.176			0.285		15.87	15.87	15.87	0.18		2231		
Patricia Rd.																					
110+50 - 113+00	37.5			28	1012.3	-984.2			0.233					20.98	20.98	20.98	0.23		1128		
Kathryn Rd.																					
118+25 - 119+ 51	55.6			42	154.1	-112.4			0.075					6.77	6.77	6.77	0.08		364		
Deer Path Rd.																					
128+80 - 129+ 50	112.1			84	63.7	20.4								0.00	0.00	0.00	0.00				
River Rd.																					
140+50 - 141+ 50	121.7			91	2.1	89.2			0.019					1.70	1.70	1.70	0.02		91		
Town Line Rd.																					
146+00 - 149+ 50	794.8			596	544.4	51.7			0.380			0.050		34.19	34.19	34.19	0.38		2082		
IL 72																					
1191+61 - 1192+ 50	354.4			266	0.0	265.8															
SUB-TOTAL =										1.80	12.26										
TOTAL	101700	27153	56036	75795	158678	-56036	22733.2	1.41	28.63	5.30	14.06	5.30	16.83	4380	4380	4380	28.63	23.55	197901	7192	

NOTES:
 * Fertilizer applied to: Class 1, Class 2A, Class 4A (Articulated Block Mat Only), Class 7 (Special)
 ** Hydraulic Mulch application rate of (4,000 lbs./acre)
 Mulch Method 2 Areas = Seeding Class 1, Prairie Mitigation Area (Class 4 & Class 5A), & Tree Mitigation Area (Class 7 (Special))
 Erosion Control Blanket Areas = Class 2A, Class 4A (Non-Articulated Block Revetment Mat Areas)