

# SUB-BASE SCHEDULE

Location	Remarks	Area	Breaker Run Depth	CA-02 Depth	CA-06 Depth	31100910	31100935	31100965	70028415	35101400
						Sub-base Granular Type A 12"	Sub-base Granular Type A 18"	Sub-base Granular Type A 24"	Geotechnical Reinforcement	Aggregate Base Course, Type B
		Sq Yd	Inch	Inch	Inch	Sq Yd	Sq Yd	Sq Yd	Sq Yd	Tons
IL 2 (Oregon to Byron)										
LT/RT Sta 680 + 00 to 684 + 89	Mainline	3327.8		9	3	3327.8			3327.8	
LT/RT Sta 684 + 89 to 690 + 00	Mainline	2831.7		9	3	2831.7				
LT/RT Sta 690 + 00 to 703 + 39	Mainline	7054.1		9	3	7054.1				
LT/RT Sta 703 + 39 to 709 + 89	Mainline	3424.0		9	3		3424.0			
LT/RT Sta 709 + 89 to 720 + 00	Mainline	5871.8		9	3	5871.8				
LT/RT Sta 720 + 00 to 720 + 39	Mainline	308.6		9	3	308.6				
LT/RT Sta 721 + 74 to 731 + 39	Mainline w/ Mud Creek	8052.5		9	3	8052.5				
LT/RT Sta 731 + 39 to 736 + 39	Mainline	2634.2		9	3	2634.2			2634.2	
LT/RT Sta 736 + 39 to 740 + 39	Mainline	2107.3		9	3	2107.3				
LT/RT Sta 740 + 39 to 741 + 89	Mainline	790.2		9	3	790.2			790.2	
LT/RT Sta 741 + 89 to 747 + 89	Mainline	3038.4	21		3			3038.4		
LT/RT Sta 747 + 89 to 749 + 89	Mainline	970.8	21		3			970.8		
LT/RT Sta 749 + 89 to 750 + 00	Mainline	55.1	21		3			55.1		
LT/RT Sta 750 + 00 to 754 + 39	Mainline w/ Indian Cove	2776.5	21		3			2776.5		
LT/RT Sta 754 + 39 to 769 + 20	Mainline	6983.3	21		3			6983.3		
LT/RT Sta 770 + 76 to 780 + 00	Mainline	4668.1		9	3	4668.1			4668.1	
LT/RT Sta 780 + 00 to 789 + 39	Mainline	5529.7	21		3			5529.7		
LT/RT Sta 789 + 39 to 795 + 00	Mainline	3303.7	21		3			3303.7		
LT/RT Sta 795 + 00 to 798 + 89	Mainline	2290.8	21		3			2290.8		
LT/RT Sta 798 + 89 to 802 + 89	Mainline	2358.3		9	3	2358.3				
LT/RT Sta 802 + 89 to 806 + 89	Mainline	2984.6	21		3			2984.6		
LT/RT Sta 806 + 89 to 810 + 39	Mainline	1804.0		9	3	1804.0				
LT/RT Sta 810 + 39 to 817 + 39	Mainline	3404.8	21		3			3404.8		
LT/RT Sta 817 + 39 to 825 + 00	Mainline	3537.4		9	3	3537.4				
LT/RT Sta 825 + 00 to 840 + 00	Mainline	7638.1	21		3			7638.1		
LT/RT Sta 840 + 00 to 855 + 00	Mainline	8841.8		9	3	8841.8			8841.8	
LT/RT Sta 855 + 00 to 870 + 00	Mainline	7623.1	21		3					
LT/RT Sta 870 + 00 to 885 + 00	Mainline	7432.0		9	3	7432.0				
LT/RT Sta 885 + 00 to 900 + 00	Mainline	7091.4		9	3	7091.4				
LT/RT Sta 900 + 00 to 909 + 39	Mainline	5228.7		9	3	5228.7				
LT/RT Sta 909 + 39 to 912 + 62	Mainline	1738.3	21		3			1738.3		
LT/RT Sta 912 + 62 to 912 + 94	Mainline	28.6	21		3			28.6		
LT/RT Sta 915 + 87 to 920 + 89	Mainline	2931.2		9	3	2931.2				
LT/RT Sta 920 + 89 to 926 + 89	Mainline	3608.2	21		3			3608.2		
LT/RT Sta 926 + 89 to 930 + 00	Mainline	1831.4		9	3	1831.4				
LT/RT Sta 930 + 00 to 940 + 39	Mainline	6127.1		9	3	6127.1				
LT/RT Sta 940 + 39 to 947 + 39	Mainline	4122.2		9	3	4122.2			4122.2	
LT/RT Sta 947 + 39 to 952 + 89	Mainline	3237.7		9	3	3237.7				
LT/RT Sta 952 + 89 to 958 + 39	Mainline	3519.3	21		3			3519.3		
LT/RT Sta 958 + 39 to 960 + 00	Mainline	1164.2		9	3	1164.2				
LT/RT Sta 960 + 00 to 966 + 39	Mainline w/ Deer Path	4682.7		9	3	4682.7				
LT/RT Sta 966 + 39 to 971 + 89	Mainline	3767.8	21		3			3767.8		
LT/RT Sta 971 + 89 to 975 + 00	Mainline	1832.8		9	3	1832.8				
LT/RT Sta 975 + 00 to 990 + 00	Mainline	7678.0		9	3	7678.0				
LT/RT Sta 990 + 00 to 1005 + 00	Mainline	7480.9		9	3	7480.9				
LT/RT Sta 1005 + 00 to 1020 + 00	Mainline	8983.1		9	3	8983.1				
LT/RT Sta 1020 + 00 to 1023 + 39	Mainline	1996.3		9	3	1996.3				
LT/RT Sta 1023 + 39 to 1025 + 89	Mainline	1472.2	21		3			1472.2		
LT/RT Sta 1025 + 89 to 1035 + 00	Mainline	5525.5		9	3	5525.5				
LT/RT Sta 1035 + 00 to 1048 + 39	Mainline	7948.7		9	3	7948.7				
LT/RT Sta 1048 + 39 to 1053 + 96	Mainline	2857.7		9	3	2857.7			2857.7	
LT/RT Sta 1053 + 96 to 1068 + 00	Mainline	9787.4		9	3	9787.4			9787.4	
SIDEROADS										
LT/RT Sta 88 + 50 to 89 + 11	Town Hall Rd.	160.8		9	3					109.9
LT/RT Sta 96 + 50 to 98 + 72	Camling Rd.	824.7		9	3				824.7	563.6
LT/RT Sta 110 + 85 to 113 + 00	Patricia Rd.	539.6		9	3					368.7
LT/RT Sta 118 + 25 to 119 + 16	Kathryn Rd.	237.8		9	3					162.5
LT/RT Sta 140 + 81 to 141 + 50	River Rd.	188.9		9	3					129.1
LT/RT Sta 146 + 00 to 149 + 18	Town Line Rd.	1127.0		9	3					770.1
TOTALS						152127	3424	53110	37854	2104

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUB-BASE SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
0:\pw_work\PWIDOT\CUSHMANBW\dms31213\dms31213.dgn	6608avr.dgn	DRAWN -	REVISED -			742	37R-4	OGLE	867	65	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	REVISED -			CONTRACT NO. 64E17		ILLINOIS FED. AID PROJECT			
PLOT DATE = Wed Mar 31 08:36:05 2010	DATE -	REVISED -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.			