

PAVEMENT MARKING SCHEDULE

LOCATION	LT / RT	REMARKS	LENGTH (FT)	X7800600	X7800610	X7800610	X7800640	X7800650	X7800650	X7800680	70300220
				URETHANE PVT. MARKING - LETTERS & SYMBOLS, SPECIAL (SQ FT)	URETHANE PVT. MARKING LINE 4" (WHITE) (FT)	URETHANE PVT. MARKING LINE 4" (YELLOW) (FT)	URETHANE PVT. MARKING LINE 8" (WHITE) (FT)	URETHANE PVT. MARKING LINE 12" (WHITE) (FT)	URETHANE PVT. MARKING LINE 12" (YELLOW) (FT)	URETHANE PVT. MARKING LINE 24" (WHITE) (FT)	TEMP. PVT. MARKING LINE - 4" (FT)
IL 2 (Oregon to Byron)											
ISLANDS / TURN BAYS											
680 + 00 to 687 + 70	LT/RT	MEDIAN OUTSIDE LINES	1539		1539						
	LT/RT	MEDIAN INSIDE LINES	1267		1267						
	LT/RT	MEDIAN DIAGONALS	202					202			
680 + 00 to 682 + 10	LT	TURKEY TRACKS	210				54				
714 + 61 to 721 + 43	LT/RT	MEDIAN OUTSIDE LINES	1158		1158						
	LT/RT	MEDIAN INSIDE LINES	1069		1069						
	LT/RT	MEDIAN DIAGONALS	166					166			
719 + 90 to 721 + 43	RT	TURKEY TRACKS	152				40				
721 + 43 to 722 + 22	LT	MEDIAN OUTSIDE LINES	431		431						
	LT	MEDIAN INSIDE LINES	191		191						
	LT	MEDIAN DIAGONALS	17					17			
721 + 43 to 722 + 22	RT	TURN BAY LINE (MUDD CREEK)	79				79				
	CL	1 - LT. TURN ARROWS	-	15.6							
722 + 22 to 723 + 83	LT	MEDIAN LINES	324			324					
722 + 22 to 723 + 83	RT	TURN BAY LINE (MUDD CREEK)	161				161				
	CL	3 - LT. TURN ARROWS	-	46.8							
724 + 55 to 725 + 36	CL	MEDIAN OUTSIDE LINES	170			170					
	CL	MEDIAN INSIDE LINES	165			165					
	CL	MEDIAN DIAGONALS	46					46			
724 + 57 to 727 + 31	LT	TURN BAY LINE (MUDD CREEK RD.)	274				274				
	LT	5 - RT. TURN ARROWS	-	78							
725 + 36 to 728 + 31	CL	MEDIAN OUTSIDE LINES	1153			1153					
	CL	MEDIAN INSIDE LINES	768			768					
	CL	MEDIAN DIAGONALS	105					105			
750 + 89 to 752 + 90	RT	TURN BAY LINE (INDIAN COVE)	200				200				
	RT	3 - RT. TURN ARROWS	-	46.8							
804 + 00 to 806 + 24	LT	TURN BAY LINE (TOWN HALL RD.)	224				224				
	LT	3 RT. TURN ARROWS	-	46.8							
814 + 22 to 815 + 77	RT	TURKEY TRACKS	155				40				
815 + 77 to 817 + 92	RT	TURN BAY LINE (OVERLOOK NO. 2)	214				214				
	RT	4 - RT. TURN ARROWS	-	62.4							
883 + 42 to 884 + 98	RT	TURKEY TRACKS	156				40				
884 + 98 to 886 + 98	RT	TURN BAY LINE (OVERLOOK NO. 3)	200				200				
	RT	3 - RT. TURN ARROWS	-	46.8							
904 + 99 to 907 + 16	LT	TURN BAY LINE (CAMLING RD.)	217				217				
907 + 16 to 908 + 65	LT	TURKEY TRACKS	149				38				
	LT	3 - RT. TURN ARROWS	-	46.8							
960 + 63 to 962 + 23	LT	TURN BAY LINE (KATHRYN RD.)	160				160				
	LT	3 RT. TURN ARROWS	-	46.8							
965 + 40 to 967 + 40	LT	TURN BAY LINE (DEER PATH RD.)	200				200				
	LT	3 - RT. TURN ARROWS	-	46.8							
1052 + 38 to 1060 + 19	LT/RT	MEDIAN OUTSIDE LINES	1572			1572					
	LT/RT	MEDIAN INSIDE LINES	652			652					
	LT/RT	MEDIAN DIAGONALS	99					99			
1055 + 15 to 1056 + 68	RT	TURKEY TRACKS	153				40				
1056 + 68 to 1060 + 19	RT	TURN BAY LINE (IL 72)	350				350				
	CL	4 - LT. TURN ARROWS	-	62.4							
1060 + 78 to 1067 + 95	LT/RT	MEDIAN OUTSIDE LINES	1442			1442					
	LT/RT	MEDIAN INSIDE LINES	1386			1386					
	LT/RT	MEDIAN DIAGONALS	252				252				
1061 + 47 to 1065 + 46	LT	TURN BAY LINE (IL 72)	399				399				
1065 + 46 to 1066 + 95	LT	TURKEY TRACKS	149				38				
	LT	5 - RT. TURN ARROWS	-	78							
MUDD CREEK ISLAND											
6 + 65 to 9 + 52	LT	MEDIAN OUTSIDE LINES	584			584					
	LT	MEDIAN INSIDE LINES	554			554					
	LT	MEDIAN DIAGONALS	50					50			
9 + 20 to 723 + 63	RT	ISLAND OUTSIDE LINES	184				184				
	RT	ISLAND INSIDE LINES	143					143			
CAMLING RD. ISLAND											
97 + 63 to 99 + 57	LT	MEDIAN OUTSIDE LINES	392			392					
	LT	MEDIAN INSIDE LINES	310			310					
	LT	MEDIAN DIAGONALS	38					38			
IL 72 ISLAND											
1191 + 86 to 1192 + 98	LT	MEDIAN LINES	227			227					
	LT	MEDIAN DIAGONALS	23					23			
1192 + 70 to 1061 + 47	LT	ISLAND OUTSIDE LINES	222				222				
	LT	ISLAND INSIDE LINES	146					146			
1192 + 68 to 1059 + 91	RT	ISLAND OUTSIDE LINES	158				158				
	RT	ISLAND INSIDE LINES	109					109			
OVERLOOK NO.2 PARKING	RT	PARKING AREA LINES	152			152					
OVERLOOK NO.3 PARKING	RT	PARKING AREA LINES	420			420					
Subtotal					91,543	68,989		398	746	233	85304
TOTAL				624	160,533		3,784	1,144			

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pwork\PIWID0T\CUSHMANBW\dms31213\060809.dgn	060809.dgn	DRAWN -	REVISED -			742	37R-4	OGLE	867	74	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64E17					
PLOT DATE = Wed Mar 31 06:36:08 2010		DATE -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			