IL RTE 2
PROP. CURVE 70360
PI STA. = 820+26.92
Δ = 41° 40′ 07″ (LT)
D = 3° 57′ 05″
R = 1,450.00′
T = 551.80′
L = 1,054.52′
E = 101.44′
e = 5.6%
P.C. T.R. = 39′
P.C. S.E. RUN = 144′
P.T. S.E. RUN = 183′ ROTATION AT STA. 826+51.65
P.C. STA. = 814+75.13
P.T. STA. = 825+29.65

IL RTE 2
PROP. CURVE 70370
PI STA. = 833+30.82
Δ = 22° 09′ 14″ (RT)
D = 1° 54′ 35″
R = 3,000.00′
T = 587.32′
L = 1,159.97′
E = 56.95′
e = 3.9%
P.C. S.E. RUN = 138′ ROTATION AT STA. 826+51.65
P.T. T.R. = 58′
P.T. S.E. RUN = 150′
P.C. STA. = 827+43.50
P.T. STA. = 839+03.47

WILLIAM H. & MABLE M. ASHELFORD TRUSTEE

MATCH LINE STA. 818+00

CONST. LIMITS

12′

820+00

EXISTING R.O.W.

PROPOSED R.O.W.

TEMPORARY EASEMENT

24′

820+64.89
20.00′ RT

CONST. LIMITS

8′ PCC SHOULDER

825+00

IL RTE 2

825+00

830+00

CONST. LIMITS

831+00.75
12.00′ LT

CONST. LIMITS

MATCH LINE STA. 832+00

X - TREE REMOVAL

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
R.T. OF WAY CHECKED
CADD FILE NAME
NOTE BOOK
NO. ____
BY
DATE

PROFILE
SURVEYED
PLOTTED
PROFILE CHECKED
B.M. NOTED
STRUCTURE NO(TYPE CHKD
NOTE BOOK
NO. ____
BY
DATE

2.82′
1281
0′ V.C.

+50.00El. 682.74

ELEVATION 683.00

-0.03%

695 690 685 680 675 670 665

818+00	819+00	820+00	821+00	822+00	823+00	824+00	825+00	826+00	827+00	828+00	829+00	830+00	831+00	832+00
680.73 / 685.82	680.58 / 685.48	681.15 / 685.16	681.02 / 684.87	681.01 / 684.59	681.14 / 684.33	681.48 / 684.09	681.69 / 683.87	681.86 / 683.67	682.05 / 683.49	682.13 / 683.33	682.01 / 683.18	681.83 / 683.06	681.78 / 682.96	681.76 / 682.88	681.89 / 682.81	681.88 / 682.77	681.89 / 682.74	681.73 / 682.73	681.81 / 682.71	681.22 / 682.70	680.21 / 682.68	679.86 / 682.67	679.66 / 682.65	679.77 / 682.64	679.64 / 682.62	679.49 / 682.61	678.80 / 682.59	676.54 / 682.57

STA. 818+00 to 832+00
EARTH EX. = 5950 CU.YDS.
EMB. = 3282.4 CU.YDS.
WASTE = 1180.1 CU.YDS.

FILE NAME = c:\pw_work\PWIDOT\GRANTPM\dms31213\d0660[illegible]plrl.dgn	USER NAME = grantpm	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ′ / IN.	CHECKED -	REVISED -
	PLOT DATE = Tue Mar 30 11:42:55 2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 2

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-4	OGLE	867	99
		CONTRACT NO. 64E17		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		